

COLOR SELECTION:

Color Selection base on Following Manufacturers:  
Vinyl Composition Tile – Armstrong Standard Excelon Imperial Texture  
Vinyl Sheet Flooring – Armstrong Medinpoint Homogeneous Sheet  
Rubber Base – Burke Mercer  
Ceramic Tile Floor – Daltile Mosaic Tile 3"x3"  
FRP Wainscot – Kemlite Glasbord-P

	<u>Carpet</u>	<u>Resilient Flooring</u>	<u>Rubber Base</u>	<u>Ceramic Tile</u>	<u>Fiberglass Reinforced Plastic (FRP)</u>	<u>Corian Counter Top</u>
Administration Building						
Entry, Vestibule, Hallways	Blue Ridge 9547 Jungle Sky	51905 hazelnut	261 Taupe	.	.	.
District Engineer, Assistant District						
Engineer, Manager, Administration	Blue Ridge 9547 Jungle Sky	"	"	.	.	.
Records		"	"	.	.	.
Storage		"	"	.	.	.
Break Room		"	"	.	.	.
Computer Server Room		"	"	.	.	.
Electrical Room		"	"	.	.	.
Utility		"	"	.	Glasboard Pearl Gray(48)	.
Women's Toilet (Sheet Vinyl)		87703 white sand	208 Light Gray	.	Glasboard Pearl Gray(48)	White
Private Toilet (Sheet Vinyl)		"	"	.	Glasboard Pearl Gray(48)	.
Men's Toilet				Pumice D336	Glasboard Pearl Gray(48)	White
Design Building						
Construction Engineer, Vestibule		51839 fortress white	150 Naugat	.	.	.
Design Branch		51932 lunar blue	506 Tahoe	.	.	.
Design Engineer		51932 lunar blue	506 Tahoe	.	.	.
Vault		"	"	.	.	.
Print Room		"	"	.	.	.
Toilet				Pumice D336	Glasboard Pearl Gray(48)	.
Survey Trailer						
Survey Crew		51901 taupe	597 Mocha	.	.	.
Office		51839 fortress white	150 Naugat	.	.	.
Foyer		"	"	.	.	.
Lab Building						
Maintenance Engineer		51932 lunar blue	506 Tahoe	.	.	.
Vestibule		51932 lunar blue	506 Tahoe	.	.	.
Construction		51839 fortress white	150 Naugat	.	.	.
Lab Office		"	"	.	.	.
Toilet				NIC	NIC	.

GENERAL NOTES:

- THIS PROJECT INVOLVES REPLACING EXISTING FLOOR COVERINGS WITH NEW. WORK INCLUDES REMOVING AND DISPOSING ASBESTOS FLOOR TILES, CERAMIC TILES, VINYL COMPOSITION TILES AND CARPET, AND REPLACING WITH NEW MATERIAL AS NOTED IN THE PLANS; REPLACING TOILET PARTITIONS AND FIXTURES; INSTALLING CABINETS AND SHELVING; ADJUSTING ELECTRICAL FLOOR OUTLETS AND SWITCHES; AND PROVIDING TEMPORARY ELECTRICAL AND TELEPHONE SERVICE TO A STATE FURNISHED TEMPORARY OFFICE TRAILER.
- ALL MATERIAL AND WORKMANSHIP SHALL CONFORM TO THE DRAWINGS AND SPECIFICATIONS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS AND JOB SITE CONDITIONS PRIOR TO CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES TO EXISTING FACILITIES AS A RESULT OF THE NEW WORK. DAMAGES SHALL BE REPAIRED OR REPLACED TO IT'S ORIGINAL CONDITION.
- TEMPORARY RELOCATION OF ALL FREESTANDING FURNITURE WILL BE BY THE STATE, EXCEPT WHERE NOTED OTHERWISE.
- WORK SHALL BE DONE IN PHASES OR AFTER HOURS TO AVOID DISRUPTION OF BASEYARD OPERATIONS. PHASING SHALL BE AS FOLLOWS:  
PHASE 1 – SURVEY TRAILER AND LAB OFFICE  
PHASE 2 – CONSTRUCTION AND MAINTENANCE ENGINEER  
PHASE 3 – CONSTRUCTION ENGINEER AND DESIGN ENGINEER  
PHASE 4 – DESIGN BRANCH (PARTIAL)  
PHASE 5 – DESIGN BRANCH (PARTIAL)  
PHASE 6 – ASSISTANT DISTRICT ENGINEER, DISTRICT ENGINEER AND VESTIBULE  
PHASE 7 – REMAINDER OF ADMINISTRATION BUILDING
- SEAL ALL AC UNITS DURING ASBESTOS REMOVAL WORK.
- REMOVE AND REINSTALL EXISTING FLOOR JUNCTION BOX COVERS UPON FLOORING REPLACEMENT.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
No.	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

MITSUNAGA & ASSOCIATES

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION  
**GENERAL NOTES**  
**COLOR SELECTION**  
**HILO BASEYARD RENOVATIONS**  
**REPLACE EXISTING ASBESTOS**  
**FLOOR TILES and CARPET**  
**Project No. HWY-H-04-04M**  
Scale: As Noted      Date: March 9, 2005  
SHEET No. T-2 OF 6 SHEETS