

ARTICLE XI - MOBILIZATION AND DEMOBILIZATION

11.1 GENERAL - The work consists of furnishing at the job site, plant, equipment, materials, labor and appliances and performing all work in connection with mobilization and demobilization for the job in accordance with this article of the specifications.

11.2 DESCRIPTION

- A. Mobilization shall include setting up, ready for use, all plant, equipment and necessary materials at the job site.
- B. Providing temporary barricades as required for Harbor operations during construction.
- C. Demobilization shall include the removal of all the Contractor's plant and equipment and surplus material from the job site. The cleanup of the job site, satisfactory to the Construction Engineer, shall also be included in this article.

11.3 PAYMENT - Payment for Mobilization and Demobilization shall not be made separately but shall be incidental to applicable items in the Proposal Schedule.