

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11G-01-04	2007	3	9

GENERAL NOTES

1. The scope of work for this project consists of: constructing grated drop inlets and an outlet structure, and installing drainage culverts and concrete gutters.
2. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
3. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
4. Dressing of shoulder shall consist of clearing, grubbing, grading, reshaping and compacting the unpaved shoulders with suitable material as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items.
5. All saw cutting work shall be considered incidental to the various contract items.
6. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting construction operations.
7. Any pavement striping/markings damaged by the Contractor as a result of his operations shall be replaced by the Contractor at no cost to the State.
8. Contractor shall dispose or deliver any removed material at no cost to the State.
9. The Contractor shall be held liable for any damages incurred to the existing utilities as a result of his operations. All damaged portions shall be replaced in accordance with the Standards and Specifications of the affected utility company at the Contractor's expense.

DRAINAGE NOTES

1. Existing drainage systems will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to accomplish maintenance of flow. The cost shall be incidental to the various contract items.
2. The Contractor shall verify the locations of all existing culverts and utilities in the field. Any existing culverts and utilities damaged during construction shall be repaired or replaced by the Contractor at his own expense.
3. For added reinforcing around existing and new culverts, see Standard Plan H-04.
4. Concrete shall be Class A unless otherwise noted.
5. Chamfer all exposed concrete edges  $\frac{3}{4}$ ".

ORIGINAL PLAN	DATE
NOTED BY	12/01/06
DESIGNED BY	
CHECKED BY	
IN CHARGE	

01/2/07

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

NOTES

MAMALAHOA HIGHWAY DRAINAGE IMPROVEMENTS  
Vicinity of Kananelu Bridge  
Project No. 11G-01-04

Date: December, 2006