

ORIGINAL PLAN

SURVEY PLOTTED BY

DATE

TRACED BY

NOTED BY

QUANTITIES BY

CHECKED BY

N.

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE										
STATION	RIGHT	LEFT	TYPE	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		OTHER	RM-3 W/O POST
					W/POST	W/O POST	W/POST(S)	W/O POST		
PROJECT NO. P-1957										
832+27		●	R1-1-A	1	1					1
832+69	●		R1-1-A	2		1	1			2
832+77	●		R4-2-A	1			1			1
834+70		●	"Adopt-A-Highway Litter Control Next 2 Miles"	1		1	1		1	2
834+91	●		"Adopt-A-Highway Litter Control Next 2 Miles"	1		1	1		1	2
837+69	●		W14-3	1			1			1
837+69		●	R4-1-A	1			1			1
839+47		●	W2-1-A	1	1					1
911+00	●		W2-2(LX(R)-B	1	1					1
913+15	●		R4-1-A	1			1			1
913+15		●	W14-3	1			1			1
918+53		●	R4-2-A	1			1			1
918+65		●	R1-1-A	1	1					1
920+87		●	R2-1(55)-B	1			1			1
928+75	●		R4-2A	1			1			1
929+00		●	W2-2(LX(R)-B	1	1					1
938+80	●		W14-3	1			1			1
938+80		●	R4-1-A	1			1			1
953+75	●		R4-1-A	1			1			1
953+75		●	W14-3	1			1			1
960+75	●		W1-2(L)	1	1					1
963+75		●	R4-2A	1			1			1
964+00	●		R2-5a	1	1					1
964+50	●		W2-2(L)	1	1					1
968+00		●	R2-1(55)-B	1			1			1
968+00	●		R2-1(45)-B	1			1			1
970+00	●		W1-8	1	1					1
970+75	●		W1-8	1	1					1
971+20		●	R1-1-A	1	1					1
971+50	●		W1-8	1	1					1
972+45	●		W1-8	1	1					1
973+05	●		W1-8	1	1					1
974+05	●		W1-8	1	1					1

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE										
STATION	RIGHT	LEFT	TYPE	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		OTHER	RM-3 W/O POST
					W/POST	W/O POST	W/POST(S)	W/O POST		
975+05	●		W1-8	1	1					1
978+00	●		W1-2 (R)	1	1					1
978+50		●	W2-1	1	1					1
985+50 thru 988+50		●	W1-8	6	6					6
PROJECT NO. P-1829				Sta. 386+50 (AH) = Sta. 988+80.41 (BK)						
385+00		●	W1-8	2	2					2
382+50	●		W1-2 (R) w/ W13-1(35)	2	1	1				1
378+10	●		W1-8	1	1					1
376+10	●		W1-8	1	1					1
373+90	●		W1-2 (L) w/ W13-1(35)	2	1	1				1
373+60		●	W1-3 (R) w/ W13-1(25)	2	1	1				1
369+70 thru 368+80		●	W1-8	4	4					4
365+80	●		W1-1 (R) w/ W13-1(25)	1	1					1
365+50		●	W2-2 w/Supplemental Street Sign	2	1	1				1
363+70	●		R1-1 w/ Street Name Sign	1	1					1
363+40	●		W14-1	1	1					1
361+35	●		W2-2 w/Supplemental Street Sign	1	1					1
359+60	●		W1-4 (R) w/ W13-1(35)	1	1					1
359+60		●	D-1 (SOUTH POINT /12 MILES) 6'x4'	1			1			2
359+00	●		ml.6 (11)	1	1					1
357+00	●		D-2 (VOLCANO 40/KONA 50) 8'x3'	1			1			2
356+90		●	R1-1 w/ Street Name Sign	1	1					1

MILEPOST MARKER SCHEDULE			
EXISTING STATION	RIGHT	LEFT	MILE MARKER
PROJECT NO. 11E-01-10M			
STA 834+01		●	MILE 73.0
STA 886+40		●	MILE 72.0
STA 940+28		●	MILE 71.0
TOTALS			3

NOTE: All MILEPOST MARKERS SHALL BE BI-DIRECTIONAL D10-7 ROUTE INDICATORS SHALL BE CONSIDERED INCIDENTAL TO ITEM NO. 632.6000, MILEPOST MARKER WITH POST.

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11E-01-10M	2010	28	32

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SIGN SCHEDULE

MAMALAHOA HIGHWAY GUARDRAIL REPAIRS

Vicinity of Kahuku

Project No. 11E-01-10M

Scale: NTS

Date: May, 2010

SHEET No. 1 OF 1 SHEETS