

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11B-01-96M	1996	31	32

REFLECTOR MARKER SUMMARY	
DESCRIPTION	QUANTITY
RM - 3 (Yellow) Without Post	90
With Flex Post (Bi-Directional)	510
TYPE II OBJECT MARKER Without Post	200
RM - 4 With Post	12

ROUTE AND MILEPOST MARKER SCHEDULE					
PROJECT	STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE INSTALL TYPE A ASSEMBLY
WPH 8-F	213+59	●		M1-6D (11)	1 1
	213+59		●	M1-6D (11)	1 1
	129+78		●	M1-6D (11)	1 1
	130+18	●		M1-6D (11)	1 1
	52+94		●	M1-6D (11)	1 1
	52+94	●		M1-6D (11)	1 1
TOTALS				6	6

PAVEMENT MARKING SUMMARY	
DESCRIPTION	QUANTITY
THERMOPLASTIC EXTRUSION or TAPE, TYPE I 4-Inch Pavement Stripe (Yellow)	9,700 L.F.
Double 4-Inch Pavement Stripe (Yellow)	20,000 L.F.
THERMOPLASTIC EXTRUSION or TAPE, TYPE II 4-Inch Pavement Stripe (White)	66,000 L.F.
THERMOPLASTIC EXTRUSION or TAPE, TYPE III 12-Inch Pavement Stripe (White)	240 L.F.
PAVEMENT MARKERS Type C	1,700 Each
Type D	1,300 Each
Type H	350 Each
Type J	1,300 Each
THERMOPLASTIC EXTRUSION or TAPE, TYPE III Crosswalk	2 Lanes

PROJECT	STATION	LEFT	RIGHT	MILE POST D10-5 (12"X36") MILE POST NO. (RTE. NO.)	REMOVE INSTALL WITH POST
F-2(3)	249+67		●	109 (11)	1 1
WPH 8-F	197+00		●	108 (11)	1 1
	142+52		●	107 (11)	1 1
	89+77		●	106 (11)	1 1
NRH 8-E	36+96		●	105 (11)	1 1
	36+96		●	KM 169 (11)	1 1
TOTALS				6	5

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
NOTE BOOK	
QUANTITIES BY	
CHECKED BY	
N. 7/brams2	
dd3/lyne	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULE

HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: NoneDate: May, 1996

SHEET No. 1 OF 1 SHEETS