

SURVEY PLOTTED BY

DATE

.....

DRAWN BY

.....

TRACED BY

.....

NOTED BY

.....

QUANTITIES BY

.....

CHECKED BY

.....

ORIGINAL PLAN

.....

NOTE BOOK

.....

No. 7112471

dd3/mr/96

RECONSTRUCTION AREA SCHEDULE							
PROJECT NO.	STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
FAP 8-G	262+65	262+65	3		15	6	90
	250+93	250+48		10	45	4	180
	250+48	250+38		5	10	10	100
	227+40	227+25	8		15	4	60
	222+56	221+50	2.5		106	5	530
WPH 8-F	213+15	213+00		2.5	15	5	75
	213+15	212+85	8		30	4	120
	212+85	212+63	5		22	10	220
	198+60	198+20		8	40	4	160
	198+20	197+90		5	30	10	300
	197+90	197+24		2.5	66	5	330
	197+24	196+00		5	124	10	1240
	196+92	196+75	2		17	4	68
	195+83	194+68		2	115	4	460
	194+75	193+38	2		137	4	548
	194+68	193+82		5	86	10	860
	193+82	193+55		2	27	4	108
	185+60	185+25	2		35	4	140
	183+00	182+50	2.5		50	5	250
	179+67	179+57		2.5	10	5	50
	179+57	179+12		5	45	10	450
	176+35	175+28	8.5		107	3	321
	175+28	174+80	5		48	10	480
	174+80	174+45	8.5		35	3	105
	174+45	174+00	5		45	10	450
	174+00	173+64	8.5		36	3	108
	170+65	170+50		5	15	10	150
	167+10	166+85		2	25	4	100
	166+85	166+65		5	20	10	200
	165+95	165+25		8	70	4	280
	165+05	164+60		8.5	45	3	135
	164+60	164+30		5	30	10	300
SUBTOTAL							8,968

PROJECT NO.	STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
WPH 8-F	164+30	164+00		8.5	30	3	90
	163+00	162+50		2.5	50	5	250
	162+50	162+25		5	25	10	250
	161+75	161+25		2	50	4	200
	161+25	160+95		5	30	10	300
	160+80	160+30		2	50	4	200
	160+10	159+80		2	30	4	120
	159+30	155+60		2	370	4	1480
	154+80	154+50		2	30	4	120
	154+15	153+90		2	25	4	100
	152+75	152+05		2	70	4	280
	151+60	149+00		2	260	4	1040
	149+00	148+65		3	35	6	210
	148+65	147+55		5	110	10	1100
	147+55	147+00		2	55	4	220
	147+00	146+40		5	60	10	600
	146+20	145+70	1.5		50	3	150
	145+60	145+00		8.5	60	3	180
	145+00	144+15		5	85	10	850
	144+15	143+85		2.5	30	5	150
	143+85	143+70		5	15	10	150
	143+70	143+45		8	25	4	100
	143+45	142+55		5	90	10	900
	142+10	141+00		1.5	110	3	330
	140+75	140+50		5	25	10	250
	140+50	140+20		8	30	4	120
	140+20	138+60		2	160	4	640
	138+60	138+25		5	35	10	350
	138+25	137+85		2	40	4	160
	137+60	136+95		8	65	4	260
	136+95	136+45		5	50	10	500
	136+85	136+70	5		15	10	150
SUBTOTAL							11,800

(CONTINUED)

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11B-01-96M	1996	22	32

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RECONSTRUCTION AREA
SCHEDULE

HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: NoneDate: May, 1996

SHEET No. 1 OF 4 SHEETS

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RECONSTRUCTION AREA
SCHEDULE

HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: None Date: May, 1996

SHEET No. 2 OF 4 SHEETS

RECONSTRUCTION AREA SCHEDULE

PROJECT NO.	STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
WPH 8-F	112+00	111+50	7.5		50	5	250
	111+40	109+20		2.5	220	5	1100
	109+20	108+90		5	30	10	300
	108+90	107+00		2.5	190	5	950
	108+65	107+80	2		85	4	340
	107+80	107+60	5		20	10	200
	107+00	106+50		5	50	10	500
	106+50	106+20		2.5	30	5	150
	104+65	104+15	5		50	10	500
	104+30	103+45		3	85	6	510
	103+45	103+20		5	25	10	250
	103+20	102+70		3	50	6	300
	102+20	100+90	7.5		130	5	650
	101+55	99+25		2.5	230	5	1150
	99+25	99+00		5	25	10	250
	99+00	98+85		2.5	15	5	75
	98+40	98+25		2	15	4	75
	96+90	96+00		8	90	4	360
	95+00	94+60		2.5	40	5	200
	94+80	94+40	5		40	10	400
	94+60	94+40		5	20	10	200
	94+00	93+70		2	30	4	120
	93+70	92+75	2		95	4	380
	93+35	92+25		2.5	110	5	550
	92+70	92+30	7.5		40	5	200
	91+90	91+55		2	35	4	140
	90+20	89+60		2.5	60	5	300
	90+20	90+10	5		10	10	100
	90+10	89+25	1.5		85	3	255
	88+90	88+25		2	65	4	260
	88+25	88+00		5	25	10	250
SUBTOTAL							11,265

(CONTINUED)

Scale: None Date: May, 1996

SHEET No. 2 OF 4 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY <i>X</i>	" <i>X</i>
	TRACED BY _____	" _____
	DESIGNED BY <i>X</i>	" _____
	QUANTITIES BY _____	" _____
7/11/49:gs2	CHECKED BY _____	" _____
add 3 turns		

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11B-01-96M	1996	24	32

RECONSTRUCTION AREA SCHEDULE

PROJECT NO.	STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
WPH 8-F	87+65	86+65	5		100	10	1000
	86+00	85+70		5	30	10	300
	85+60	83+65	1.5		195	3	585
	85+40	85+00		5	40	10	400
	85+00	84+00		1.5	100	3	300
	82+25	81+50	8.5		75	3	225
	77+80	76+75	5		105	10	1050
	76+40	75+15		2.5	125	5	625
	75+15	74+85		5	30	10	300
	74+85	74+50		2.5	35	5	175
	74+30	73+50	2		80	4	320
	74+30	73+50		2	80	4	320
	73+40	73+20		2	20	4	80
	72+60	72+00		2	60	4	240
	71+00	69+30	1.5		170	3	510
	70+00	69+70		2.5	30	5	150
	68+25	67+65		2	60	4	240
	67+65	67+20		5	45	10	450
	67+20	66+90		2	30	4	120
	66+27.98 EQUATION STATION						
	66+36.10						
	65+65	64+95		5	70	10	700
	64+50	64+25		3	25	6	150
	62+85	62+00		7	85	6	510
	62+80	62+00	8.5		80	3	240
	62+00	61+75	5		25	10	250
	62+00	61+75		5	25	10	250
	61+75	60+95		7	80	6	480
	60+40	60+30	3		10	6	60
	60+30	60+00	5		30	10	300
	60+20	59+95		8	25	4	100
	60+00	57+50	8.5		250	3	750
	SUBTOTAL						11,180

SURVEY PLOTTED BY

DATE

PLAN

REVISION

NOTE BOOK

QUANTITIES BY

CHECKED BY

11/11/96

11/11/96

11/11/96

11/11/96

11/11/96

11/11/96

11/11/96

PROJECT NO.	STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
WPH 8-F	59+20	58+95		5	25	10	250
	56+80	54+75	8.5		205	3	615
	56+30	56+10		5	20	10	200
	55+40	54+75		4	65	8	520
	54+75	54+50		8	25	4	100
	54+20	53+70	7.5		50	5	250
	53+70	53+50	5		20	10	200
	53+50	51+80	7.5		170	5	850
	51+65	51+10		5	55	10	550
	51+20	46+70	8		450	4	1800
	50+40	50+10		7.5	30	5	150
	50+10	50+00		5	10	10	100
	50+00	49+35		7.5	65	5	325
	47+50	47+20		8	30	4	120
HRH 8-E	46+50						
	46+30	45+60	8		70	4	280
	45+60	45+20	5		40	10	400
	45+20	44+90		8	30	4	120
	43+85	43+60	8.5		25	3	75
	42+45	42+10	2		35	4	140
	42+45	41+90		8	55	4	220
	41+90	41+70		5	20	10	200
	41+70	41+20		8	50	4	200
	41+31	40+20	8.5		111	3	333
	41+00 EQUATION STATION						
	40+94.34						
	40+35	38+50		8.5	185	3	555
	38+50	37+20		8	130	4	520
	37+90	37+20	8.5		70	3	210
	36+60	36+50	5		10	10	100
	36+60	36+35		5	25	10	250
	36+50	36+35	8		15	4	60
	SUBTOTAL						9,693

(CONTINUED)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
RECONSTRUCTION AREA SCHEDULE
HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: None Date: May, 1996

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11B-01-96M	1996	25	32

RECONSTRUCTION AREA SCHEDULE

PROJECT NO.	STATION		OFFSET FROM RD. ¢ TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
HRH 8-E	36+35	35+05		8	130	4	520
	33+85	33+70		5	15	10	150
	33+70	33+35		8	35	4	140
	32+35	31+40		7.5	95	5	475
	30+95	30+70		8	25	4	100
	30+30	30+05		8	25	4	100
	29+80	29+00		8	80	4	320
	28+30	28+10	8		20	4	80
	27+55	26+90	8		65	4	260
	27+30	26+65		8	65	4	260
	26+15	25+95	8		20	4	80
	24+60	24+15		8	45	4	180
	24+50	24+30	8		20	4	80
	23+50	22+65	8		85	4	340
	19+75	19+50		8	25	4	100
	18+70	17+80	8		90	4	360
	18+30	17+90		5	40	10	400
	16+50	16+30	8		20	4	80
	16+15	15+20	8.5		95	3	285
	15+00	14+60	8		40	4	160
	13+60	13+40		8	20	4	80
	12+90	12+60		7.5	30	5	150
	11+50	10+00	8		150	4	600
	9+00	8+70	8		30	4	120
	7+60	6+00	8		160	4	640
FAP 8-D	0+00	326+00					
	341+04 BEGIN EXCEPTION						
	356+00 END EXCEPTION						
	356+00	357+85	8.5		185	3	555
	359+20	359+90		8.5	70	3	210
	360+55	362+20		8	165	4	660
	361+60	361+75	6.5		15	3	45
SUBTOTAL						7,530	

PROJECT NO.	STATION		OFFSET FROM RD. ¢ TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
FAP 8-D	364+40	366+50		8	210	4	840
	364+90.7 EQUATION STATION						
	364+88.9						
	367+80	368+80		8	100	4	400
	369+90	370+30		8.5	40	3	120
	370+30	371+00		5	70	10	700
	371+39.9 EQUATION STATION						
	371+39.3						
	372+30	373+25		8.5	95	3	285
	374+00	375+00		8.5	100	3	300
	377+35	378+15		8	80	4	320
	378+75	379+10	8		35	4	140
	378+75	378+90		1.5	15	3	45
	378+90	379+10		5	20	10	200
	380+55	381+10		9	55	2	110
	381+70	382+25		8	55	4	220
	384+41.2 EQUATION STATION						
	384+39.4						
	383+05	388+65		8.5	560	3	1680
	389+89.2 END PROJECT						
	SUBTOTAL						5,760
	TOTAL RECONSTRUCTION AREA						81,066

SURVEY PLOTTED BY	DATE	
DRAWN BY		
TRACED BY		
NOTES BY		
QUANTITIES BY		
CHECKED BY		
ORIGINAL PLAN		
NOTE BOOK		
NO. 7134954		
dd3type		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
**RECONSTRUCTION AREA
SCHEDULE**
HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M
Scale: None Date: May, 1996
SHEET No. 4 OF 4 SHEETS