

[illegible](Continued)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SIGN SCHEDULE

HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: None Date: May, 1996

SHEET No. 1 OF 3 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY <i>X</i>	<i>X</i>
	TRACED BY	
NOTE BOOK	DESIGNED BY <i>X</i>	
	QUANTITIES BY	
	CHECKED BY	

No. *7198561*

cd3/more

STATION	LEFT	RIGHT	TYPE	SIGN TO REMAIN	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		DESTINATION SIGN PANEL (S.F.)
						W/POST	WO/POST	W/POST	WO/POST	
120+28	●	●	R8-3a(L)		2	2				
119+54	●		R1-1		1	1				
119+54	●		R3-2		1	1				
116+13	●		W(ROAD FLOODS DURING RAIN) (36"x36")		1	1				
116+13	●		W13-1(35)		1		1			
112+37	●		W14-1		1	1				
112+05	●		R1-1		1	1				
111+65	●		S1-1		1	1				
109+60		●	W(ROAD FLOODS DURING RAIN) (36"x36")		1	1				
109+60		●	W13-1(35)		1		1			
107+10	●		D-1 (HONAUNAU) (74" X20")		1					10.28
105+77		●	R2-1(45)-a (35" X 48")		1			1		
105+77	●		S4-3		1		1			
105+77	●		R2-1(25)		1	1				
105+77	●		S4-2		1		1			
104+28	●		PRIVATE ROAD	1						
104+28	●		W14-1	1						
103+97	●		R1-1		1	1				
102+66		●	R1-1		1	1				
102+06	●		S2-1		1	1				
101+44		●	S2-1		1	1				
97+69	●		R2-1(45)-a (36" X 48")		1			1		
97+26		●	S4-3		1		1	1		
97+26		●	R2-1(25)		1	1				
97+26		●	S4-2		1		1			
94+72		●	R8-3a(R)	1	1	1				
94+03		●	R8-3a(B)	1	1	1				
93+49		●	R8-3a(B)		1	1				
92+04		●	S1-1		1	1				
91+11		●	R8-3a(B)		1	1				
83+36	●		W2-2(R)		1	1				
83+36	●		D3-2 (MIDDLE KEEI RD)				1			
79+58	●		R1-1		1	1				

(Continued)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SIGN SCHEDULE

HAWAII BELT ROAD RESURFACING
KEALAKEKUA TO KIILAE
PROJECT NO. 11B-01-96M

Scale: None Date: May, 1996

SHEET No. 2 OF 3 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
NOTE BOOK	DESIGNED BY	
	QUANTITIES BY	
	CHECKED BY	
No. <i>Thresses</i>		
<i>dd3/wave</i>		

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	11B-01-96M	1996	30	32

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE

STATION	LEFT	RIGHT	TYPE	SIGN TO REMAIN	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		DESTINATION SIGN PANEL (S.F.)
						W/POST	WO/POST	W/POST	WO/POST	
36+68	●		Adopt-A-Highway	1						
36+68	●		LAW OFFICE OF IAN MATTOCH	1						
6+78	●		R2-5b(35)-a (36" X 48")		1			1		
3+31		●	R2-4(30)		1					
2+45	●		CAUTION WINDING ROAD NARROW SHOULDERS NEXT 15 MI. 25 KM. (96"x48")		1			1		32.00
0+03		●	R2-1(45)-a (36" X 48")		1			1		
0+02	●		R2-1(35)-a (36" X 48")		1			1		
0+00 326+00			FAP 8-E FAP 8-D							
326+02	●		F.A.P. 8-D/8-E	1						
329+07		●	W1-5(L)		1	1				
336+29		●	ELEV 1000 FT 305 M (24"x20")		1	1				
336+50	●		ELEV 1000 FT 305 M (24"x20")		1	1				
339+26		●	W1-3(L)		1	1				
339+26		●	W13-1(25)		1		1			
339+56		●	W1-8		1	1				
340+64		●	W1-8		2	2				
355+29	●		D-2*Kailua 19/		1					49.50
356+05	●		<- Puuhonua O Honaunau 3 R2-1(35)-a (36" X 48")		1			1		
TOTALS				20	107	75	19	10	0	91.78

SIGN NOTES

- Letter Size:
 - When letters are all uppercase, use series "E"
 - When initial uppercase letter is used in conjunction with lowercase letters, use series "E" (M) for uppercase letter.
- All signs shall conform to Section 621 of the Special Provisions and the latest editions and amendments of the following FHWA publications:
 - "Manual on Uniform Traffic Control Devices for Streets and Highways" (MUTCD)
 - "Standard Highway Signs"
 - "Standard Alphabets for Highway Signs"
- Borders, messages, arrows, symbols and shield shall conform to details as shown on the plans and as specified in the MUTCD.
- Sign messages shall be as indicated on the plan.
- All panels shall be reflectorized in accordance with Section 712.20 of the Standard Specifications. Minimum width of panels shall be 2 ft. Abutting edges of panels shall be in only one direction. If vertical abutting edges are used, no horizontal abutting edges shall be allowed and vice versa.
- Contractor shall submit all sign splicing details to the Engineer for approval. All backing for signs 4 feet by 6 feet or less shall be of one sheet.
- Paint all Sign Posts with yellow reflective paint. This work is considered as incidental to sign items.
- Existing signs not shown on these plans or listed in the Sign Schedule shall remain as posted unless otherwise directed by the Engineer. Removal and disposal of existing signs and/or posts as designated on these plans shall be incidental to the various signing items.
- All signs and posts removed are the property of the State. Contractor shall be responsible for stockpiling material at location designated by the Engineer. This work shall be considered incidental to various signing items and no separate payment shall be provided.
- Final locations of all signs shall be approved by the Engineer prior to any installation work.
- All street name plates and destination signs that are removed and installed in the same or new location shall be identical to the existing sign in size and text. The contractor shall submit Shop Drawings to the Engineer for approval prior to fabricating the sign.
- Removal of existing delineators and posts shall be considered incidental to various signing items.
- Street name plates shall be considered incidental to Item No. 621.5100, Regulatory and Warning Sign (10 square feet or less) with Posts.
- All signs shall be installed with square tube posts, unless otherwise noted.
- Destination signs shall be installed with breakaway sign posts.

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
NOTED BY	
CHECKED BY	

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
SIGN SCHEDULE
HAWAII BELT ROAD RESURFACING KEALAKEKUA TO KIILAE PROJECT NO. 11B-01-96M
Scale: None Date: May, 1996
SHEET No. 3 OF 3 SHEETS