

10-27-52  
1-14-53

Face of guardrail shall be a minimum of 6'-0" from edge of pavement.

Wood Guard Rail with  
Concrete Posts, 8'-0"  
See Std. Detail Sheet  
No. 5607.2

Construct furrow ditch as required.

Tops of cut slope are to be rounded as shown at the places indicated by the engineer. He will require that this be done in all sand, earth and conglomerate material, but not solid rock or in conglomerate that he believes will remain cemented state. Hand trimming, rounded top of cut will be paid for on the linear foot basis as per Specification. Material excavated in the shaded area will be paid under the items of Unclassified Excavation and Overhaul.

At cut sections between Sta. 24+00 and Sta. 21+00 where volcanic rock material is encountered at subgrade, excavation 6" below subgrade shall be ordered by the Engineer.  
Subgrade shall be taken as the bottom of the base course for this project.  
6" layer of select material will be required for the above mentioned sections.

Slope NOTE: On tangent section climbing lane slopes 0.015 ft. per ft. towards edge of pavement.

SUB-BASE - Subbase shall be Select Material Subbase  
24" thick, except at cut sections where rocky material is encountered at subgrade.  
All the above courses subject to Special Provisions & Specification

Special Borrow Layers may be omitted upon the discretion of the Engineer. See Special Provisions.

When super-elevation is less than .063 ft. per ft. the slope of the shoulder on the lower side is 34:12 (min.). When the super is greater than .063 ft. per ft. the shoulder slope is equal to the rate of super.

Provide extra widening on curves where called for on plans

Scale:  $3/8" = 1'-0"$

Scale:  $\frac{1}{4}'' = 1' - 0''$

Date: May, 1952

5607.2

|                        |                         |            |
|------------------------|-------------------------|------------|
| ORIGINAL<br>PLAN       | SURVEY PLOTTED BY _____ | DATE _____ |
| NOTE BOOK<br>No. _____ | DRAWN BY _____          | ____       |
|                        | TRACED BY _____         | ____       |
|                        | QUANTITIES BY _____     | ____       |
|                        | CHECKED BY _____        | ____       |
|                        | CHECKED BY _____        | ____       |