




FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-019-1(20)	2005	113	315




DETECTABLE WARNING AT CURB RAMP




TRANSITION RAMP WITH DETECTABLE WARNING



REFUGE ISLAND WITH DETECTABLE WARNING



SHARED CURB RAMP WITH DETECTABLE WARNING




END OF SIDEWALK CURB RAMP WITH DETECTABLE WARNING

TYPICAL INSTALLATION OF DETECTABLE WARNINGS

Scale: Not To Scale

NOTES:


1. Detectable warnings shall be 24 inches in the direction of travel and extend the full width of the curb ramp or flush surface (does not include flares).
2. Truncated domes shall have a diameter of 0.9 inch at the bottom, a diameter of 0.4 inch at the top, a height of 0.2 inch and a center-to-center spacing of 2.35 inches measured along one side of a square arrangement.
3. Domes shall be aligned on a square grid in the predominant direction of travel to permit wheels to roll between the domes.
4. There shall be a minimum of 70 percent contrast in light reflectance between the detectable warning and an adjoining surface, or the detectable warning shall be "safety yellow".
5. The material used to provide visual contrast shall be an integral part of the detectable warning surface.
6. The detectable warning shall be located so that the edge nearest the curb line or other potential hazard is 6 to 8 inches from the curb line.



ENLARGEMENT

DETECTABLE WARNING DETAIL

Scale: Not To Scale



DOMES SECTION



This work was prepared by me or under my supervision
Exp. 04-30-10
Neal S. Fukumoto
Wesley R. Segawa & Associates, Inc.

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
DETECTABLE WARNING DETAILS	
QUEEN KAAHUMANU HIGHWAY WIDENING HENRY ST. to KEALAKEHE PKWY - PHASE I Federal Aid Project No. NH-019-1(20)	
Scale: As Noted	Date: November 2009
SHEET No. 1 OF 1 SHEETS	