

DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HSIP-019-2(62)	2012	29	42

MONUMENT SCHEDULE													
	STATION	MONUMENT TYPE	RECONSTRUCT (613.0200)	INSTALL NEW (614.0100)	OFFSET (Ft.)	DEPTH NOTE	PROJECT	STATION	MONUMENT TYPE	RECONSTRUCT (613.0200)	INSTALL NEW (614.0100)	OFFSET (Ft.)	DEPTH NOTE
SDR 3(18) (Kaawalii)	98+09.90	CONST. MON.	1		B/L 0.00	Unknown	SDR 3(17) (Laupahoehoe)	35+47.84	R/W MON.		1	Lt. 1.24	Unknown
	100+09.96	CONST. MON.	1		B/L 0.00	Unknown		42+64.73	CONST. MON.	1	1	B/L 0.00	Unknown
	107+27.15	CONST. MON.	1		Lt. 1.32	Unknown		46+50.23	R/W MON.		1	Lt. 1.02	Unknown
	111+03.56	R/W MON.		1	Rt. 0.44	Unknown		56+53.13	R/W MON.		1	Rt. 2.04	Unknown
	112+36.99	R/W MON.		1	Rt. 0.81	Unknown		60+92.01	R/W MON.		1	Rt. 0.93	Unknown
	115+61.86	CONST. MON.	1		B/L 0.00	Unknown		63+36.11	CONST. MON.	1		Lt. 0.99	Unknown
	116+61.82	R/W MON.		1	Rt. 0.93	Unknown		64+19.55	CONST. MON.	1		Rt. 6.16	Unknown
	123+08.21	CONST. MON.	1		Rt. 0.23	Unknown		65+03.12	R/W MON.		1	Lt. 0.80	Unknown
	124+08.19	CONST. MON.	1		Rt. 0.43	Unknown		72+31.87	R/W MON.		1	Lt. 3.47	Unknown
	127+43.27	CONST. MON.	1		Rt. 0.92	Unknown							
	130+76.10	CONST. MON.	1		B/L 0.00	Unknown							
	134+55.49	CONST. MON.	1		Lt. 3.68	Unknown							
	144+21.98	CONST. MON.	1		Lt. 2.09	Unknown							
	TOTALS			10	3				TOTALS			3	7
Note: Reconstruct Right of Way Monuments to "Street Survey Monument" Standard Plan Sheet D-08.													

STRIPING AND PAVEMENT MARKING SCHEDULE									
STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION (Lin. Ft.)			PAVEMENT MARKERS (Each)		
				4" Double Yellow Stripe	8" Single White Stripe (EP)	12" White Stop Bar			
FROM	TO	LEFT	RIGHT				C	D	A
KA'AWALI'I GULCH									
91+00	148+00	N	N	5,700	11,400		287	286	
91+00	113+00	P	CLIMBING				56		220
128+00	146+00	P	CLIMBING				46		180
99+50		SIDE DRIVEWAY		25	75	16	4	2	
141+00		SIDE DRIVEWAY		25	75	16	4	2	
144+60		SIDE DRIVEWAY		25	75	16	4	2	
LAUPAHOEHOE GULCH									
30+00	82+00	N	N	5,000	10,000		252	251	
37+00	46+50	P	CLIMBING				24		90
69+00	82+00	P	CLIMBING				34		130
81+00		SIDE DRIVEWAY		25	75	16	4	2	
Rounded Totals				10,800	21,700	100	720	550	620
Item No.				629.1014	629.1012	629.1018	629.2030	629.2040	629.2080

SURVEY PLOTTED BY	DATE	
DRAWN BY		
DESIGNED BY		
QUANTITIES BY		
CHECKED BY		
ORIGINAL PLAN		
NOTE BOOK		
FILED		
DATE		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULES

HAWAII BELT ROAD
Safety Improvements

Laupahoehoe Gulch and Ka'awali'i Gulch
Federal Aid Project No. HSIP-019-2(62)

Scale: 1" = 40'
Date: June, 2012

SHEET No. 1 OF 1 SHEETS