

DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-019-2(067)	2014	24	41

STRIPING AND PAVEMENT MARKING SCHEDULE

STATION		Traffic Regime		Linear Feet	Thermoplastic Extrusion (L.F.)						Thermoplastic Extrusion (Each)		Pavement Markers (Each)					
FROM	TO				4" Double Yellow Stripe	4" Single Yellow Stripe	4" Single White Stripe	8" Single White Stripe	12" White Stripe	12" Single Yellow Stripe	12" White Stripe 12"x10' Crosswalk	Pavement Arrow (Standard Left Turn)	Pavement Arrow (Standard Right Turn)	A	C	D	H	J
		Lt.	Rt.	(ft)														
145+00	149+00	Median		400	800		800			400					20		40	
149+00	155+00	N	N	600	600		1,200								30	30		
155+00	161+00	Median		600	1,200		1,200			600					30		60	
161+00	173+00	N	N	1,200	1,200		2,400								60	60		
173+00	176+00	Median		300	600		600			300					15		30	
176+00	188+50	N	N	1,250	1,250		2,500								63	63		
188+50	197+82.73 0+00	N	P	933		933	1,866								47	23	23	93
197+82.73 0+00	6+00	P	P	600			1,200								30	15		60
6+00	15+00	P	N	900		900	1,800								45	23	23	90
15+00	24+00	N	P	900		900	1,800								45	23	23	90
24+00	39+00	N	P	1,500			3,000								2	1	1	
39+00	85+60	N	N	4,660	4,660		9,320								233	233	1	
85+60	90+00	Median		440	880		880			440					24		45	
90+00	98+00	N	N	800	800		1,660								40	40		
98+00	109+00	P	N	1,100		1,100	2,200								55	28	28	110
109+00	141+00	N	N	3,200	3,200		6,400								160	160		
141+00	148+40	P	N	740		740	1,480								37	19	19	74
148+40	157+00	N	N	860	860		1,720								43	43		
157+00	165+00	N	P	800		800	1,600								40	20	20	80
165+00	170+60 70+55	N	N	560	560		1,120								28	28		
170+60 70+55	3+71.01	N	N	6,684	6,684		13,368								334	334		
148+30	153+30	Turn		500			500		16			2			25			
154+00	156+00	Turn		200			200		16			2			10			
160+00	167+50	Turn		750			750		16			3			38			
161+50	167+60	Turn		610			610		16				2		31			
168+00	174+00	(2) Turn		1,200			1,200		32			3	2		60			
45+00	86+00	Climbing		4,100										410	103			
167+70		(4) Island		---				480	400									
18+00		(3) Island		---				400	300									
153+60		Sideroad			25		70		16									
153+60		Sideroad			25		70		16									

Continued

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTED	DRAWN BY	
DESIGNED BY	TRACED BY	
CHECKED BY	DESIGNED BY	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRIPING AND PAVEMENT
MARKING SCHEDULE

HAWAII BELT ROAD RESURFACING
Pepeekeo to Hakalau
Federal Aid Project No. NH-019-2(067)

Scale: NoneDate: March, 2014

SHEET No. 1 OF 2 SHEETS

DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-019-2(067)	2014	25	41

STRIPING AND PAVEMENT MARKING SCHEDULE

STATION		Traffic Regime		Linear Feet	Thermoplastic Extrusion (L.F.)						Thermoplastic Extrusion (Each)		Pavement Markers (Each)					
FROM	TO				4" Double Yellow Stripe	4" Single Yellow Stripe	4" Single White Stripe	8" Single White Stripe	12" White Stripe	12" Single Yellow Stripe	12" White Stripe 12"x10' Crosswalk	Pavement Arrow (Standard Left Turn)	Pavement Arrow (Standard Right Turn)	A	C	D	H	J
167+70		Sideroad		25		70		16										
167+70		Sideroad		25		70		16										
188+00		Sideroad		25		70		16										
188+00		Sideroad		25		70		16										
10+00		Sideroad		25		70		16										
50+50		Sideroad		25		70		16										
51+00		Sideroad		25		70		16										
60+00		Sideroad		25		70		16										
74+60		Sideroad		25		70		16										
75+00		Sideroad		25		70		16										
134+00		Sideroad		25		70		16										
155+00		Sideroad		25		70		16										
170+20		Sideroad		50		140		32										
49+50		Sideroad		25		70		16										
49+50		Sideroad		25		70		16										
40+00		Sideroad		25		70		16										
25+00		Sideroad		25		70		16										
18+00		Sideroad		25		100		32										
18+00		Sideroad		25		100		32										
153+60		Crosswalk								100								
168+00		Crosswalk								50								
		Bridge Approach					6,000											
Estimated Totals				23,044	5,373	62,114	6,880	1,180	1,340	150	10	4	410	1,626	1,141	271	597	
Item No.				629.1014	629.1013	629.1011	629.1012	629.1018	629.1019	629.1018	629.1030	629.1040	629.2020	629.2030	629.2040	629.2060	629.2050	

NOTES: 1. Final striping layout to be determined by the Engineer in the field.
2. Striping quantities shown in this table may not match final field layout.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRIPING AND PAVEMENT
MARKING SCHEDULE

HAWAII BELT ROAD RESURFACING
Pepeekeo to Hakalau
Federal Aid Project No. NH-019-2(067)

Scale: As Shown Date: March, 2014

SHEET No. 2 OF 2 SHEETS

SURVEY PLOTTED BY
DATE
DRAWN BY
DESIGNED BY
QUANTITIES BY
CHECKED BY

ORIGINAL PLAN
NOTE BOOK
Helix
6/14/2014