

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HE5-0100(27)	1985	5	47

PAVEMENT STRIPING AND MARKER SUMMARY

SITE	STATION		DESCRIPTION		±	E.P.(WHITE)		PAVEMENT MARKERS				
	FROM	TO	LT.	RT.	YELLOW	LT.	RT.	D	H	J		
1	180+60	65			2,508	2507	2515	126				
	182+00	205+20	No Passing	No Passing	2,320	2320	2320	#7				
	205+20	205+60	No Passing	Passing	300	300	300	8	8	32		
	65	9+85			440	361	372	13	12	48		
2	322+71	326+83			413	413	413	13	10	24		
	324+50	330+80	Passing	No Passing	630	630	630	#6	#9	60		
	330+80	347+00	No Passing	No Passing	1,620	1620	1620	81				
	326+83	348+60			2,231	2,042	2,038	100				
3	372+17	392+72			1,325	1,272	1,332	64				
	380+00	391+50	No Passing	No Passing	1,150	1,150	1,150	58				
					6,917	6,595	6,670	325	22	72		
TOTALS					6,020	6,020	6,020	280	23	92		

For pavement markings, signs and reflector markers plans, see Plan Sheet Nos. 14 & 15.

SIGN SUMMARY

SITE	STATION		DESCRIPTION		OBJECT	RELOCATE	REFLECTIVE	CHEVRON
	FROM	TO	LT.	RT.	MARKER	W/POST	MARKER W/POST	W/POST
1	197+66			RM-1			1	
	195+85		65 Mile Post			1		
	182+40	186+30	RM-1				7	
	184+00	186+60		RM-1			6	
	193+40	208+10	RM-1				19	
	193+90	197+00		RM-1			6	
	200+10	203+70		RM-1			6	
	206+00			RM-1			1	
2	328+82		W2-2			1		
	345+50		W1-4L W13-1(35)			1		
	344+46			Type II	1			
	321+75	327+36		RM-1			6	
	330+70	331+50		RM-1			2	
	326+80	335+60	RM-1				13	
	340+70	352+30	RM-1				11	
	327+60	330+00		W1-8R				4
	327+60	330+00	W1-8L					4
	337+00	340+00		W1-8R				6
	337+00	340+00	W1-8L					6
	333+50			RM-1			1	
	380+75			W1-4L W13-1(35)		1		
3	382+20	386+50		RM-1			7	
	390+00	390+70		RM-1			2	
	386+60	389+30		W1-8R				5
	386+60	389+30	W1-8L					4
	382+02		RM-1				1	
	380+42		RM-1				1	
TOTALS					1	3	85	29

GUARD RAIL SUMMARY

SITE	STATION		LIN. FT. (MINUS BCT)	END TREATMENT	
	FROM	TO		APPROACH	TRAILING
1	182+80 L	186+20 L	333	C	F
	183+50 R	186+90 R	328.7	BCT	F
	193+80 L	206+70 L	1,337.3	G	F
	193+70 R	197+30 R	354.7	BCT	F
	199+00 R	207+20 R	437.5	C	F
2	326+00 L	346+00 L	1,973.8	BCT	
	327+00 R	331+75 R	450	BCT	F
	5	92	416.8		
3	382+00 R	388+10 R	526.2	BCT	
	385+00 R	393+15 R	587.5		G
	8	68	390	BCT	G
TOTAL			6,294.7	6	
			6,365	#BCT	1-BCT

Guard Rail with 8-foot posts shall be installed at the following locations:

Sta. 193+75± to Sta. 196+25± Lt.
Sta. 202+25± to Sta. 203+35± Lt.
Sta. 205+02.5± to Sta. 205+87.5± Lt.
Sta. 385+25± to Sta. 386+25± Rt.

Guard Rail with 8-foot posts shall be paid for under Item 606.3/10 - Guard Rail, Type 3 - Single with Steel Post.

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION
PAVEMENT STRIPING AND GUARD RAIL SUMMARY
KAWAIIAN ROAD SAFETY IMPROVEMENTS PHASE I WAIMEA TO KAWAIIAN FED. AID PROJ. NO. HE5-0100(27)
REVISION 1 Date: Feb., 1985
SHEET NO. 1 OF 2 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY _____ DATE _____	
NOTE BOOK	DRAWN BY _____	" _____
	TRACED BY _____	" _____
	DESIGNED BY _____	" _____
	QUANTITIES BY _____	" _____
No. _____	CHECKED BY _____	" _____

CRM SUMMARY ~ ESTIMATED QUANTITIES

[illegible]

A.C CURB SUMMARY ~ ESTIMATED QUANTITIES

For culvert profile and details, See Plan Sheet Nos. 10 & 11.
Drainage Facilities "A," "B," "C," "D," "E," & "F" are paid for on
a lump sum basis.

6