

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-1(18)	1995	18	30

RECONSTRUCTION AREA SCHEDULE

Station		Offset - # Rd. to Center Recon. Area		Length (L.F.)	Width (L.F.)	Approx. Area (Sq. Feet)
From	To	Left	Right			
18 +75	19 +80	6.00		105.00	12.00	1260.00
21 +00	22 +00	6.00		100.00	12.00	1200.00
22 +00	22 +75	6.20		75.00	12.40	930.00
22 +75	23 +30	6.20		55.00	12.40	682.00
23 +30	23 +70	3.00		40.00	6.00	240.00
27 +00	27 +60		3.00	60.00	6.00	360.00
27 +60	27 +75	6.00		15.00	12.00	180.00
27 +60	28 +00		6.00	40.00	12.00	480.00
27 +75	28 +00	3.00		25.00	6.00	150.00
28 +25	28 +50	6.00		25.00	12.00	300.00
28 +85	29 +15		6.00	30.00	12.00	360.00
36 +50	37 +50	3.00		100.00	6.00	600.00
40 +00	41 +00	3.00		100.00	6.00	600.00
41 +75	42 +75	6.00		100.00	12.00	1200.00
44 +00	52 +40	6.00		840.00	12.00	10080.00
69 +55	70 +10		6.00	55.00	12.00	660.00
72 +00	72 +20		6.00	20.00	12.00	240.00
74 +00	74 +80		6.00	80.00	12.00	960.00
75 +00	75 +30		6.00	30.00	12.00	360.00
77 +00	78 +00		3.00	100.00	6.00	600.00
78 +00	78 +30		6.00	30.00	6.00	180.00
89 +40	90 +35		3.00	95.00	6.00	570.00
91 +00	94 +00	6.00		300.00	12.00	3600.00
113 +60	114 +10		3.00	50.00	6.00	300.00
114 +80	115 +10	6.00		30.00	12.00	360.00
127 +75	128 +25	6.00		50.00	12.00	600.00
131 +00	133 +50		3.00	250.00	6.00	1500.00
133 +85	135 +25	3.00		140.00	6.00	840.00
134 +40	135 +00		3.00	60.00	6.00	360.00
137 +50	139 +00		3.00	150.00	6.00	900.00
140 +60	141 +80		3.00	120.00	6.00	720.00
141 +20	141 +60	6.00		40.00	12.00	480.00
143 +35	144 +00		3.00	65.00	6.00	390.00
144 +00	144 +20		6.00	20.00	12.00	240.00
144 +20	144 +50		3.00	30.00	6.00	180.00
148 +00	149 +10		3.00	110.00	6.00	660.00
149 +95	150 +55		3.00	60.00	6.00	360.00

RECONSTRUCTION AREA SCHEDULE

Station		Offset - # Rd. to Center Recon. Area		Length (L.F.)	Width (L.F.)	Approx. Area (Sq. Feet)
From	To	Left	Right			
155 +15	158 +00		8.00	285.00	16.00	4560.00
162 +35	163 +10	9.00		75.00	6.00	450.00
167 +00	167 +80		3.00	80.00	6.00	480.00
167 +80	170 +00		6.00	220.00	12.00	2640.00
179 +70	180 +00		3.00	30.00	6.00	180.00
183 +50	184 +00		3.00	50.00	6.00	300.00
185 +00	187 +50		3.00	250.00	6.00	1500.00
188 +90	191 +50		3.00	260.00	6.00	1560.00
193 +00	193 +25		3.00	25.00	6.00	150.00
195 +00	197 +15		6.00	215.00	12.00	2580.00
199 +30	200 +15		3.00	85.00	6.00	510.00
208 +90	209 +20		6.00	30.00	12.00	360.00
232 +00	233 +55		6.00	155.00	12.00	1860.00
232 +20	233 +55	6.00		135.00	12.00	1620.00
Airport Access Road * 0+00/233 +37						
0 +12	2 +30		6.00	218.00	12.00	2616.00
0 +12	2 +30	6.00		218.00	12.00	2616.00
TOTAL						57664.00

* Station 233+37 on Queen Kaahumanu Highway is equivalent to Station 0+00 on the Airport Access Road. Stations run along the Centerline of Airport Access Road, Perpendicular to Queen Kaahumanu Highway.

SURVEY PLOTTED BY _____ DATE _____
 DRAWN BY _____
 NOTE BOOK _____
 QUANTITIES BY _____
 CHECKED BY _____

STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION
PAVEMENT RECONSTRUCTION
SCHEDULE
 QUEEN KAAHUMANU HWY RESURFACING
 HONOKOHAU TO KEAHOLE
 F.A. PROJECT NO. STP-019-1(18)
 Date: Feb., 1995
 SHEET No. 1 OF 1 SHEETS