



Not To Scale

	CONSTRUCTIO	/	SI	GN SCHEDULE	-
ROAD AND	ROUTE 19 BASE LINE STATION **	LEFT	RIGHT	ITEM No. 621.7121 (no posts)	ITEM No. 621.7120 (two posts)
Hawaii Belt Road	19+50				CW20-Id
	19+50			CW13-1(35)	,
	<i>19+50</i>				CG20-2
	<i>14+50</i>				CG20-I(2)
Kulana Street	10+00				CW20-Id
Kululia Sil eel	10+00		·		CG20-2
Davidsa Ctroot	6+00		•		CW20-Id
Paukaa Street	6+00				CG20-2
Nahala Street	. 25+00 • CW2	CW20-Id			
Nationa Street	25+00	-	•		CG20-2
Wainaku Street	4+00	-	•		CW20-Id
	4+00				CG20-2

(Continued at right)

ROAD AND LOCATION *	ROUTE 19 BASE LINE STATION **	LEFT	RIGHT	ITEM No. 621.7121 (no posts)	ITEM No. 621.7120 (two posts)
Hau Street	48+00		•		CW20-Id
	48+00		•		CG20-2
Pukihae Street	75+00	•			CW20-Id
	75+00	•			CG20-2
Hawaii Belt Road	82+42	•			CG20-I(2)
	86+50		•		CG20-2
	86+50	•		CW13-1(35)	
	86+50	•			CW20-1c
Total Construction Signs				2	18

- * Final locations of all signs to be determined in the field by the Engineer .
- ** Signs erected on side roads must be located 50' (Min.), from E.P. of Hawaii Belt Road .

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION

<u>CONSTRUCTION SIGN</u> <u>PLAN **#** SCHEDULE</u>

HAWAII BELT ROAD RESURFACING KULANA STREET TO WAILUKU BRIDGE

F. A. Project No. STP-019-2(34)

Scale: As Shown

Date: March, 1995 SHEET No. 1 OF 1 SHEETS