

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-2(34)	1995	27	40

RECONSTRUCTION AREA SCHEDULE							
PROJECT NO.	STATION		OFFSET FROM RD. # TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
SDR 3(1)	82+42.06	81+42			100	24	2,400
	81+27	81+11	9.0		16	6	96
	80+87	80+73	3.0		14	6	84
	80+56	80+31	6.0		25	12	300
	79+40	79+18	6.0		22	12	264
	79+18	78+80	10.0		38	4	152
	78+80	78+66	6.0		14	12	168
	78+10	78+00		3.0	10	6	60
	77+77	77+71	3.0		6	6	36
	76+63	76+43	6.0		20	12	240
	76+61	76+38		6.0	23	12	276
	75+76	75+33		3.0	43	6	258
	75+56	75+33	6.0		23	12	276
	75+23	75+11		9.5	12	5	60
	74+99	74+95			4	12	48
	74+69	74+59		10.0	10	4	40
	73+05	72+78		10.0	27	4	108
	72+78	72+68		6.0	10	12	120
	74+00	72+58	6.0		142	12	1,704
	69+85	69+70		10.0	15	4	60
	68+84	68+71	9.0		13	6	78
	68+72.98	67+72.98			100	24	2,400
	65+77.02	64+77			100	24	2,400
	63+45	63+25		2.0	20	6	120
	62+50	62+30		6.0	20	12	240
	61+50	61+18		8.0	32	4	128
	60+85	60+30	8.0		55	4	220
BEGIN DIVIDED HIGHWAY (MAKAI LANE)							
	57+55	57+30	6.0		25	5.5	138
	57+09	56+76		5.0	33	13	429
	53+60	52+84	9.0		76	6	456
	50+19	48+50	9.0		169	6	1,014

PROJECT NO.	STATION		OFFSET FROM RD. # TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
	FROM	TO	LEFT	RIGHT			
SDR 3(1)	48+05	47+84	9.0		21	6	126
	47+40	47+05	9.0		35	6	210
	46+62	46+02	6.0		60	12	720
	44+14	43+47	6.0		67	12	804
	43+15	43+00	6.0		15	12	180
BEGIN DIVIDED HIGHWAY (MAUKA LANE)							
	47+85	47+50		6.0	35	12	420
	47+50	47+30		2.0	20	4	80
	44+11	43+29		6.0	82	12	984
	42+65	42+40		8.5	25	7	175
END DIVIDED HIGHWAY							
	41+75	41+59	10.0		16	8	128
	40+74	40+46	7.0		28	4	112
	31+85	31+36	6.0		49	12	588
	31+17	31+00	6.0		17	12	204
	28+50	26+55	8.5		195	7	1,365
	25+60	25+50	8.5		10	7	70
	24+50	23+80	9.0		70	6	420
	23+00	22+00	9.0		100	6	600
	18+50	17+20		6.0	130	12	1,560
	16+78	16+26		5.0	52	17	884
	12+65	11+60			105	24	2,520
	11+43	0+00			1,143	24	27,432
	0+00	-4+00			400	24	9600
SDR 3(4)	21+02	35+36			1,434	24	34,416
TOTAL							97,971

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
	NOTE BOOK	
	CHECKED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RECONSTRUCTION
AREA SCHEDULE

HAWAII BELT ROAD RESURFACING
KULANA STREET TO WAILUKU BRIDGE
F. A. Project No. STP-019-2(34)

Scale: None Date: March, 1995

SHEET No. 1 OF 1 SHEETS