

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-2(32)	1995	15	26

LANE RECONSTRUCTION SCHEDULE							
Street Name	Station		Offset From C.L.		Length ( L.F.)	Width ( L.F.)	Area (Sq. Feet)
	From	To	Left	Right			
Silva Street							
	91+75	92+60		20	85	varies	1,250
Kalaniana'ole Ave.							
	2+65	-2+45		6	510	12	6,120
					TOTAL:	7,370 S.F.	
					APPROX. TOTAL:	820 S.Y.	

PAVING FABRIC AREAS							
Street Name	Station		Offset From C.L.		Length ( L.F.)	Width ( L.F.)	Approx. Area (Sq. Feet)
	From	To	Left	Right			
Airport Traffic Circle Area							
	91+75	92+60				varies	2,800
Kalaniana'ole Ave.							
	2+65	-1+35	6		400	12	550
TOTAL:							3,350 S.F.
APPROX. TOTAL:							400 S.Y.

RECONSTRUCTION OF SHOULDER AREA SCHEDULE							
Street Name	Station		Side of Road		Length ( L.F.)	Width ( L.F.)	Area (Sq. Feet)
	From	To	Left	Right			
Kamehameha Ave.							
	74+37	50+28	●		1,091	4	4,364
	60+45	63+95	●		350	12	4,200
Kalaniana'ole Ave.							
	52+80	55+50	●		270	4	1,080
Silva Street							
	86+02	101+62	●	●	*	varies	18,816
	86+02	101+62	●	●	1,350	3	4,050
	101+30	101+62	●		*	varies	500
TOTAL:							33,010 S.F.
APPROX. TOTAL:							3,700 S.Y.

NOTES:

- For Reconstruction of Shoulder Area Details see Sheet No. 9 .
- For Reconstruction Area Details see Sheet No. 10 .
- Reconstruction areas shown are approximate. Final limits and locations shall be determined in the field by the Engineer .
- Kamehameha Avenue, Sta. 73+50, to Kalaniana'ole Avenue, Sta. 55+50, shall be coldplaned and resurfaced according to the typical sections. See Sheet No. 4 for details.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	X
dd/mh	DESIGNED BY	
N. Shihab	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

PAVEMENT & SHOULDER  
RECONSTRUCTION SCHEDULE

KAMEHAMEHA AVENUE RESURFACING  
WAILOA BRIDGE TO KUHIO WHARF  
F.A. PROJECT NO. STP-019-2(32)

Date: April, 1995