

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-2(35)	1995	35	39

CENTERLINE AND REFERENCE SURVEY MONUMENT SCHEDULE

PROJECT	STATION	MONUMENT TYPE	Adjust Existing Item No. 613.0110	Reconstruct Existing Item No. 613.0120	CENTERLINE OFFSET * (FT.)	EXISTING DEPTH (FT.)
FA-F 14B(1)	6+12.92	R/W P.C.		1	1.30 Lt.	0.14
	8+46.25	S.C. MON.		1	1.03	unknown
	10+46.25	C.S. MON.		1	1.90 Lt.	0.07
	12+79.58	R/W P.T.		1	0.50 Lt.	0.06
	36+44.68	P.O.T. MON.		1	---	0.07
	<u>58+65.45</u> <u>58+69.95</u>	CONST. P.C. R/W P.C.	≠	1	---	0.00
	60+91.03	P.I. MON.	≠	1	3.10 Rt.	0.00
	<u>63+07.45</u> <u>63+11.95</u>	CONST. P.T. R/W P.C.	≠	1	---	0.00
	91+93	P.O.T. MON.	≠	1	---	0.00
	99+73.26	T.S. MON.	≠	1	0.25 Lt.	0.00
	<u>100+74.96</u> <u>100+73.46</u>	CONST. P.C. R/W P.C.	≠	1	0.35 Lt.	0.00
	101+73.26	S.C. MON.	1		0.35 Lt.	0.00
	<u>110+28.82</u> <u>110+29.22</u>	-BACK -AHEAD	≠	1	0.30 Rt.	0.00
	134+25.08	P.O.T. MON.	≠	1	---	0.00
	155+01	P.O.T. MON.	1	1	---	0.00
	184+87.48	P.O.T. MON.		1	0.50 Lt.	0.34
	<u>198+00</u> <u>0+00</u>	Change Projects		1	0.25 Rt.	0.36
SDR 3(2)	11+57.93	P.C. MON.		1	0.40 Lt.	0.28
	18+43.76	P.T. MON.		1	0.30 Lt.	0.30
	46+68.11	P.C. MON.	≠	1	---	0.00
	60+29.98	P.T. MON.	≠	1	---	0.00
	73+44.49	P.C. MON.	≠	1	---	0.00
TOTALS			<u>0</u> 13	<u>21</u> 9		

MILEPOST AND ROUTE MARKER SCHEDULE

PROJECT	STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE	INSTALL TYPE A ASSEMBLY
FA-F 14B(1)	6+08		●	MI-6 (19)	1	1
	146+00	●		MI-6 (19)		1
	156+00		●	MI-6 (19)		1
	163+75	●		MI-6 (19)		1
	170+49		●	MI-6 (19)	1	1
	170+55	●		MI-6 (19)	1	
SDR 3(2)	51+95	●		MI-6 (19)	1	1
	52+10		●	MI-6 (19)	1	1
TOTALS					5	7
PROJECT	STATION	LEFT	RIGHT	MILE POST D10-4 (12"X24") MILE POST NO. (RTE. NO.)	REMOVE	INSTALL WITH POST (BI-DIRECTIONAL)
FA-F 14B(1)	40+99		●	8 (19)	2	1
	93+24		●	9 (19)	2	1
	148+05		●	10 (19)	2	1
SDR 3(2)	1+14		●	11 12 (19)	2	1
	53+93		●	12 13 (19)	2	1
TOTALS					10	5

UTILITY SCHEDULE

PROJECT	STATION	OFFSET FROM CENTERLINE		TYPE	REMARKS
		LEFT	RIGHT		
FA-F 14B(1)	7+13	16.2		SMH	2.0' dia.
	8+84	16.0		SMH	2.0' dia.
	9+93	16.0		SMH	2.0' dia.
	10+89	17.2		SMH	2.0' dia.
	12+38	18.2		SMH	2.0' dia.
	14+51	13.6		SMH	2.0' dia,
	14+91		27.0	WM	In Roadway
	23+01		12.0	WM	1.0' dia.
	23+03	19.6		WM	1.2' x 1.4'
	33+17		21.5	WM	1.0' dia.
	33+20		15.9	WM	1.2' x 1.4'
	159+60	16.3		SMH	2.0' dia.
	161+60	17.6		SMH	2.0' dia.

Legend : SMH - Sewer Manhole 8 Total
WM - Water Meter 5 Total

PAVEMENT MARKING SUMMARY

DESCRIPTION	QUANTITY
<i>THERMOPLASTIC EXTRUSION or TAPE, TYPE I</i>	
Double 4-Inch Pavement Stripe (Yellow)	15,315 13,700 L.F.
4-Inch Pavement Stripe (Yellow)	3,233 4,900 L.F.
8-Inch Pavement Stripe (White)	1,085 1,070 L.F.
Arrow	20 21 Ea.
<i>THERMOPLASTIC EXTRUSION or TAPE, TYPE II</i>	
Double 4-Inch Pavement Stripe (Yellow)	2,565 1,400 L.F.
4-Inch Pavement Stripe (White)	40,587 35,300 L.F.
8-Inch Pavement Stripe (White)	16,889 17,200 L.F.
12-Inch Pavement Stripe (Yellow)	484 70 L.F.
<i>THERMOPLASTIC EXTRUSION or TAPE, TYPE III</i>	
Stop Bar	557 400 L.F.
Crosswalk	7 2 Lanes
Word	8 Ea.
4-Inch Edge Line Extension (White)	1,931 780 L.F.
<i>PAVEMENT MARKERS</i>	
Type A	648 510 Ea.
Type C	1,742 1,610 Ea.
Type D	1,128 1,000 Ea.
Type H	258 240 Ea.
Type J	1,236 1,400 Ea.

LEGEND FOR
AS-BUILT POSTINGS

	Squiggly line for as-built deletion
	Double line for as-built deletion
Roadway	Text for as-built posting

MISCELLANEOUS SCHEDULES

HAWAII BELT ROAD RESURFACING
PAPAIKOU TO PEPEEKEO
F.A. PROJECT NO. STP-019-2(35)

Scale: None Date: April, 1995

SHEET No. 1 OF 1 SHEETS

"AS-BUILT"

35

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY <u>X</u>	" <u>X</u>
<i>diagram</i>	TRACED BY _____	" _____
<i>drawings</i>	DESIGNED BY <u>X</u>	" _____
	QUANTITIES BY _____	" _____
	CHECKED BY _____	" _____
	BY <u>S₁</u>	" <u>S₂</u>