

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-2(35)	1995	31	39

RECONSTRUCTION AREA SCHEDULE (Continued)								
PROJECT NO.	STATION		OFFSET FROM RD. ¢ TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROXIMATE AREA (SQ. FT.)	
	FROM	TO	LEFT	RIGHT			RECONSTRUCT	GEOTEXTILE
SDR 3(2)	12+80	12+90		3	10	12	120	
	21+15	21+40		6	25	6	150	
	21+15	21+40	3		25	6	150	
	25+80	26+50	3		70	6	420	
	27+15	27+25	6		10	12	120	
	27+15	27+25		6	10	12	120	
	27+75	27+85	6		10	12	120	
	27+75	27+85		6	10	12	120	
	28+70	29+10		6	40	12	480	
	29+40	35+00	6		560	12	-----	6,720
	29+68	36+34		6	665	12	7,992	
	36+34	37+18			71	30	2,130	
	37+18	44+00		6	682	12	8,184	
	40+85	46+56	6		571	12	6,852	
	46+60	60+20	18		1360	12	-----	16,320
	60+30	72+55	18		1225	12	14,700	
	68+00	69+00	6		100	12	-----	1,200
	73+00	73+80	9		80	6	480	
	75+7	77+26	6		219	12	2,628	
	77+26	85+90	12		864	24	20,736	
	85+87	90+55		6	468	12	5,616	
	85+90	90+82	18		492	12	5,904	
	91+00	92+00		9	100	6	600	
	TOTAL AREAS						240,024	31,248

REFLECTOR AND OBJECT MARKER SUMMARY	
DESCRIPTION	QUANTITY
RM -2 (Yellow) Without Post Steel Post	100 178
RM-3 (Yellow) Without Post Steel Post Flex Post	4 30 136
RM-3 (Bi-Directional/Yellow) Steel Post Flex Post	70 26
RM- 4 Steel Post	24
TYPE II OBJECT MARKER Without Post	1

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
QUANTITIES BY	DESIGNED BY	
CHECKED BY	NOTED BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

RECONSTRUCTION AREA AND
REFLECTOR MARKER SCHEDULES

HAWAII BELT ROAD RESURFACING
PAPAIKOU TO PEPEKEO
F.A. PROJECT NO. STP-019-2(35)

Scale: NoneDate: April, 1995

SHEET No. 2 OF 2 SHEETS