

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-019-2(37)	1995	26	36

CENTERLINE AND REFERENCE SURVEY MONUMENT SCHEDULE

PROJECT	STATION	MONUMENT TYPE	CENTERLINE AND REFERENCE MON.		CENTERLINE OFFSET (FT.)	EXISTING DEPTH (FT.)
			RECON.	ADJUST		
SDR 3(6)	182+20	PROJ. MON.		1	0.00	0.10
	214+49.06	P.T. MON.	1		1.50 R	0.25
	267+45.99	P.C. MON.	1		0.00	level
	288+85.56	PROJ. MON.		1	0.40 L	0.12
F-019-2(2)	2+18	P.I. MON.		1	8.80 L	0.12
	4+40.54	P.T. MON.		1	0.10 L	0.12
	9+48.82	P.C. MON.		1	0.10 R	0.12
	23+52.82	P.T. MON.		1	0.35 L	level
	48+09.98	P.C. MON.		1	0.30 L	level
	61+92.76	P.T. MON.		1	0.10 R	level
	69+64.80	PROJ. MON.		1	0.20 L	0.10
SDR 3(18)	72+01.51	P.C. MON.		1	0.00	level
	81+01.51	P.T. MON.		1	0.20 R	level
	98+08.68	P.C. MON.	1		0.80 L	0.30
	100+08.68	S.C. MON.	1		0.20 L	0.25
	107+26.62	P.C.C. MON.	1		0.25 L	0.25
	111+03.76	C.S. MON.	1		0.10 R	0.22
	112+38	C.L. MON.	1		0.20 L	0.25
	115+63	C.L. MON.	1		1.20 R	0.25
	116+61.98	S.C. MON.	1		0.90 R	0.30
	123+09.32	C.S. MON.	1		0.35 R	0.15
	124+09	C.L. MON.	1		0.70 R	0.25
	127+45	C.L. MON.	1		0.10 L	0.23
	130+78	C.L. MON.	1		0.10 R	0.20
	134+58	C.L. MON.	1		3.50 L	0.20
	144+29	C.L. MON.	1		2.20 L	0.35
TOTAL			15	11		

ROUTE MARKER AND MILEPOST SCHEDULE

PROJECT	STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE	INSTALL w/ TYPE A ASSEMBLY
SDR 3(6)	229+89	●		M1-6 (19)	1	1
	229+90		●	M1-6 (19)	1	1
F-019-2(2)	0+17		●	M1-6 (19)	1	1
	0+18	●		M1-6 (19)	1	1
SDR 3(18)	69+70		●	M1-6 (19)	1	1
TOTALS					5	5
PROJECT	STATION	LEFT	RIGHT	MILE POST D10-5(12"X36") MILE POST NO. (RTE. NO.)	REMOVE	INSTALL WITH POST (BI-DIRECTIONAL)
SDR 3(6)	169+57	●		33 (19)	1	1
	222+04	●		32 (19)	1	1
	275+34	●		31 (19)	1	1
F-019-2(2)	38+42	●		30 (19)	1	1
SDR 3(18)	91+03	●		29 (19)	1	1
	143+92	●		28 (19)/45 KM *	1	1
TOTALS					6	6

* Contractor shall submit shop drawings of Kilometer Post Sign to the Engineer for approval prior to fabrication. Payment for kilometer sign plates shall be incidental to Item No.621.7620 - Mile Post Marker and Route Number Plate .

PAVEMENT MARKING SUMMARY

DESCRIPTION	QUANTITY
PAVEMENT MARKERS	
Type A	1,725 Each
Type C	1,775 Each
Type D	1,175 Each
Type H	150 Each
Type J	650 Each
THERMOPLASTIC EXTRUSION or TAPE, TYPE I	
Double 4-Inch Pavement Stripe (Yellow)	20,000 L.F.
4-Inch Pavement Stripe (Yellow)	4,500 L.F.
THERMOPLASTIC EXTRUSION or TAPE, TYPE II	
4-Inch Pavement Stripe (White)	37,700 L.F.
8-Inch Pavement Stripe (White)	14,000 L.F.
12-Inch Pavement Stripe (White)	150 L.F.
12-Inch Pavement Stripe (Yellow)	200 L.F.
THERMOPLASTIC EXTRUSION or TAPE, TYPE III	
12-Inch Pavement Stripe (Yellow)	250 L.F.

SURVEY PLOTTED BY	DATE
DRAWN BY	
TRACED BY	
NOTED BY	
QUANTITIES BY	
CHECKED BY	

ORIGINAL PLAN	
NOTE BOOK	
DATE	
BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULES

HAWAII BELT ROAD RESURFACING
Kaala Bridge to Kaawalii Gulch
F. A. PROJECT NO. STP-019-2(37)

Scale: NoneDate: Nov., 1994

SHEET No. 1 OF 1 SHEETS