

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	19A-01-97M	1997	27	29

CENTERLINE & REFERENCE SURVEY MONUMENT SCHEDULE					
PROJECT	STATION	MONUMENT TYPE	Adjust Centerline and Reference Mon. (ITEM NO. 613.0110)	Reconstruct Centerline and Reference Mon. (ITEM NO. 613.0120)	EXISTING DEPTH (FT.)
FAP F-011-1(14)					
	10+00	P.O.T.	1		0.08
BD-3267-02-63					
	21+13.08	P.C.	1		0.09
	30+00	P.O.C.	1		0.08
	35+00	*	1		0.00
	40+00	P.O.C.		1	0.07
	50+00	P.O.C.		1	unknown
	55+95.01	P.T.	1		0.11
	67+00	P.O.T.	1		0.07
	77+50.12	P.C.	1		0.10
	84+26.44	P.T.		1	unknown
	95+00	P.O.T.	1		0.10
	105+00	P.O.T.	1		0.10
	121+47	**	1		0.00
	121+50	***	1		0.10
	126+05.57 /0+00.11	P.O.T.		1	unknown
TOTAL			11	4	

Note: All monuments on centerline except Sta. 40+00 (1.2 ft. right).

- * Centerline Makala Blvd.
- ** Centerline Honokohau Harbor Rd.
- *** Centerline Kealakehe Parkway

ROUTE MARKER SCHEDULE							
PROJECT	STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE	INSTALL TYPE A ASSEMBLY	INSTALL TYPE B ASSEMBLY
FAP F-011-1(14)							
	5+00		●	M1-6D (19)	1	1	
	5+93	●		M1-6C (190)/M6-1L M1-6D (11)/M6-3	1		1
BD-3267-02-63							
	119+60		●	M3-1/M1-6D (19)/M6-3	1	1	
	123+35	●		M3-3/M1-6D (19)/M6-3	1	1	
TOTALS					4	3	1

MILEPOST MARKER SCHEDULE						
PROJECT	STATION	LEFT	RIGHT	MILE POST * D10-5 (12"x36") MILE POST(RTE)	REMOVE	INSTALL WITH POST
BD-3267-02-63						
	45+11	●		99 (19)	1	1
	97+89	●		98 (19)	1	1
TOTALS					2	2

* - Bidirectional

ORIGINAL PLAN	SURVEY PLATTED BY	DATE
NOTE BOOK	DRAWN BY	5/13/97
INSTRUMENT	BY	
CHECKED BY	QUANTITIES BY	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULE

QUEEN KA'AHUMANU HIGHWAY RESURFACING
PALANI ROAD TO HONOKŌHAU HARBOR
PROJECT NO. 19A-01-97M

Scale: NoneDate: May, 1997

SHEET No. 1 OF 1 SHEETS