



Notes For Work Through Kaawalii Gulch:

- 1. The work for this site consists of removing loose and unstable rocks on the slopes and disposing of the rock debris.
- 2. Contractor shall be responsible for thoroughly familiarizing themselves with the site conditions prior to tendering a bid. Cut slopes may exceed typical ½: 1 ratio in some areas and cut banks reach heights exceeding 100'. Site access and staging areas are very limited.

STATE OF HAWAI'I

DEPARTMENT OF TRANSPORTATION

HIGHWAYS DIVISION

DICAL SECTION & NOTE

TYPICAL SECTION \$ NOTES

HAWAI'I BELT ROAD

EMERGENCY SLOPE STABILIZATION

Vicinity of Kaawalii Gulch

PROJECT NO. 19H-01-97M

Scale: As Noted

Date: May, 1997

PLAN DRAWN
TRACEI

SHEET No. 1 OF 1 SHEETS