

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	19A-01-98	2000	12	22

PAVEMENT MARKING SUMMARY		
DESCRIPTION	QUANTITY	
PAVEMENT MARKERS		
TYPE A _____	50	EA.
TYPE C _____	140	EA.
TYPE D _____	10	EA.
TYPE H _____	100	EA.
TAPE - THERMOPLASTIC EXTRUSION		
4-INCH PAVEMENT STRIPE (WHITE) _____	4000	L.F.
4-INCH PAVEMENT STRIPE (YELLOW) _____	100	L.F.
8-INCH PAVEMENT STRIPE (WHITE) _____	750	L.F.
12-INCH PAVEMENT STRIPE (WHITE) _____	120	L.F.
12-INCH PAVEMENT STRIPE (YELLOW) _____	1000	L.F.
DOUBLE 4-INCH PAVEMENT STRIPE (YELLOW) _____	1800	L.F.
CROSSWALK MARKINGS _____	8	LANES
PAVEMENT ARROW _____	4	EA.
PAVEMENT SYMBOLS _____	2	EA.
PAINT		
ASPHALT CONCRETE CURB (WHITE) _____	210	L.F.

TRAFFIC SIGN SUMMARY					
SIGN NO.	MESSAGE	QUANTITY			
		10 SQ. FT. OR LESS		GREATER THAN 10 SQ. FT.	
		W/POST	W/O POST	W/POSTS	W/O POSTS
W11-1		1			
R10-12	LEFT TURN YIELD ON GREEN ●		2		
R1-2	YIELD	2			
	TOTAL	3	2		

CONSTRUCTION SIGN SUMMARY				
SIGN NO.	LOCATION	MESSAGE	W/POSTS	W/O POSTS
CW20-1Ad	Sta. 51+70 Rt.	ROAD WORK AHEAD	1	
CG20-2A	Sta. 51+70 Lt.	END ROAD WORK	1	
CW20-1Ad	Sta. 76+40 Lt.	ROAD WORK AHEAD	1	
CG20-2A	Sta. 76+40 Rt.	END ROAD WORK	1	
CW20-1Ad	Hina-Lani Street 500' before the intersection of Queen Kaahumanu Highway	ROAD WORK AHEAD	1	
CG20-2A	Hina-Lani Street 500' after the intersection of Queen Kaahumanu Highway	END ROAD WORK	1	
CW13-1(35)	Sta. 51+70 Rt. & Sta. 76+40 Lt.	35 M.P.H.		2
		TOTAL	6	2

SURVEY PLOTTED BY _____	DATE _____
DRAWN BY <i>M. Takafuji</i>	
CHECKED BY _____	
QUANTITIES BY _____	
CHECKED BY _____	
ORIGINAL PLAN	
NOTE BOOK	
<i>Ida Ruby</i>	
<i>S. Sakthi</i>	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TRAFFIC SUMMARY

QUEEN KAAHUMANU HIGHWAY

Installation of Traffic Signals

at Hina-Lani Street

Project No. 19A-01-98

Date: Feb., 2000

SHEET No. 1 OF 1 SHEETS