FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAI'I	HAW.	FLH-019-1(26)	2000	17	46

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE

STATION	LEFT	RIGHT	TYPE	SIGN TO REMAIN	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		DESTINATION SIGN	
						W/POST	WO/POST	W/POST	WO/POST	SIZE (SQ. FT.)	POST INSTALL.
10+65	●		W2-2-A(L) (48" x 48")	1							
13+00	●		R2-1 (45)-a (36" x 48")		1						
16+50		●	D-1 (← Kaloko-Honokōhau National Historical Park)							49.00	W6x9.0
18+00	●		R2-1 (45)-a (36" x 48")					1			
18+00		●	R2-1 (45)-a (36" x 48")	1							
22+00		●	W11-1c (36" X 36")	1							
22+00	●		W11-1c (36" X 36")		1	1					
25+40	●		W5-4a(Watch for Bikers)(30"x30")			1					
25+56	●		R1-1-A (36" x 36")			1					
26+16	●		R1-2 (36" x 36" x 36")			1					
28+65	●		(Combined Lane) (30" x 30")			1					
32+50	●		D-2 (Kaloko-Honokōhau → National Historical Park)							49.00	W6x9.0
TOTALS				3	2	5	0	1	0	98.00	

Notes:

1. See Sheet Nos. 12 & 13 for Sign Details and Standard Sign Notes.
2. Street name sign SSN-1 shall be paid for under Item 621.500 - Regulatory and Warning Sign (10 square feet or less) w/out Posts.
3. Fabrication and installation of Supplemental Street Name sign shall be considered incidental to installation of W2-1 and W2-2 signs, as applicable.
4. Square tube sign posts required for the installation of destination signs shall be considered incidental to Item No. 621.0200 - Panel for Destination Sign.
5. W1-1 signs shall be installed with its face perpendicular to the roadway centerline.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY X	
	TRACED BY	
NOTE BOOK 8pthass	DESIGNED BY X	
No. 4fgh	QUANTITIES BY	
	CHECKED BY	

STATE OF HAWAI'I
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SIGN SCHEDULE

QUEEN KA'AHUMANU HIGHWAY
INTERSECTION IMPROVEMENTS TO
KALOKO-HONOKŌHAU NATIONAL HISTORICAL PARK
PROJECT NO. FLH-019-1(26)

Scale: None Date: Mar., 1998

SHEET No. 1 OF 1 SHEETS