

| FED. ROAD DIST. NO. | STATE | PROJ. NO. | FISCAL YEAR | SHEET NO. | TOTAL SHEETS |
|---------------------|-------|--------------|-------------|-----------|--------------|
| HAWAII | HAW. | HWY-H-08-00M | 2000 | 3 | 9 |

GENERAL NOTES

- The scope of work for this project includes of the replacement of existing Bridge Joints with Asphaltic Plug Expansion Joints; Sealing Joints in Curbs, Sidewalks & Parapets, and installing Fixed Deck Joints.*
- The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.*
- The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.*
- At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.*
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.*
- Existing drainage system will be functional at all times during construction. The Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to various contract items.*
- The contractor shall provide for access to and from all existing side streets at all times.*
- All saw cutting work shall be considered incidental to the Respective Contract items.*

| | | |
|---------------|-------------------|------|
| ORIGINAL PLAN | SURVEY PLOTTED BY | DATE |
| NOTED | DRAWN BY | X |
| DESIGNED BY | TRACED BY | |
| CHECKED BY | DESIGNED BY | |
| | CHECKED BY | |

| | |
|--|-------------------|
| STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION | |
| <u>GENERAL NOTES</u> | |
| MAULUA/PAHEEHEE/KAPUE/PUKIHAE | |
| BRIDGE JOINT REPAIRS | |
| PROJECT NO. HWY-H-08-00M | |
| Scale: none | Date: March, 2000 |
| SHEET No. 1 OF 1 SHEETS | |