

SURVEY PLOTTED BY

DATE

PLAN

DATE

TRACED BY

DATE

NOTE BOOK

DATE

QUANTITIES BY

DATE

CHECKED BY

DATE

ORIGINAL

PLAN

NOTE BOOK

QUANTITIES BY

CHECKED BY

DATE

CONSTRUCTION PROJECT NO.	STATION		LEFT / RIGHT	LENGTH OF NEW GUARDRAIL (FT.)	REFLECTORS AND OBJECT MARKERS						BRIDGE NAME	REMARKS
					RM-2 W/FLEX POST	RM-3 W/FLEX POST	RM-4 W/STEEL POST	RM-3 W/NO POST	RM-4 W/NO POST	RM-3 W/FLEX POST (BI-DIR)		
	FROM	TO										
19BC-01-71	1465+76.00	1451+93.00	L	1388	17	1	--	--	--	1	--	
	1465+24.00	1453+24.00	R	1200	16	--	--	--	--	1	--	
	1430+83.00	1424+45.00	L	638	9	2	--	--	--	1	--	
	1432+42.00	1422+82.00	R	962	13	1	--	--	--	1	--	
	1418+76.00	1411+12.00	L	763	10	2	--	--	--	1	--	
	1417+60.00	1411+24.00	R	638	9	2	--	--	--	1	--	
	1386+69.00	1376+17.00	L	1050	14	1	--	--	--	1	--	
	1382+85.00	1375+62.00	R	725	12	--	--	--	--	1	--	
	1338+77.00	1333+27.00	L	550	8	2	--	--	--	1	--	
	1300+02.00	1289+14.00	L	1088	13	2	--	--	--	1	--	
	1296+48.00	1289+62.00	R	688	9	2	--	--	--	1	--	
	1261+74.00	1251+25.00	R	1050	13	2	--	--	--	1	--	
	1261+35.00	1249+35.00	L	1200	14	2	--	--	--	1	--	
	1168+52.00	1162+40.00	R	613	9	2	--	--	--	1	--	
	1168+42.00	1161+30.00	L	713	10	2	--	--	--	1	--	
	1152+26.00	1143+70.00	R	863	12	1	--	2	--	1	--	
	1143+39.00	1140+96.94	R	255	5	--	--	2	--	1	--	Equa. Sta. 1140+96.94 / 1125+00
	1125+00.00	1124+17.00	R	83	2	1	--	--	--	1	--	Equa. Sta. 1140+96.94 / 1125+00
	860+49.00	854+11.00	L	638	9	2	--	--	--	1	--	
	845+00.00	839+12.00	L	588	8	2	--	--	--	1	--	
	678+97.00	670+10.00	L	888	11	2	--	--	--	1	--	
	644+67.00	638+43.00	R	625	9	2	--	--	--	1	--	
	521+38.00	504+84.00	L	1675	20	1	--	2	--	--	--	
	495+98.00	488+12.00	L	788	11	1	--	--	--	1	--	
	369+22.00	360+36.00	L	888	11	2	--	--	--	1	--	
	233+73.00	224+73.00	R	1025	15	--	--	2	--	2	--	
***	210+31.00	207+65.00	R	300	5	--	--	--	--	--	--	
****	1+03.70	2+66.00	L	163	3	1	--	--	--	1	--	
	2+34.00	0+96.00	R	138	3	1	--	--	--	1	--	
***	207+20.00	204+48.00	R	300	4	1	--	--	--	1	--	
	74+11.00	62+04.00	L	1200	15	1	--	--	--	1	--	
	69+54.00	64+60.00	R	525	9	1	--	2	--	1	--	
	42+59.00	38+84.00	L	375	6	2	--	--	--	1	--	
	TOTALS			24,583	334	44	0	10	--	32		

FED. ROAD DIST.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-019-1(31)	2001	32	55

Note: Left and right reference always refers to relative direction facing up-station. For Proj. No. 19BC-01-71, left refers to the maikai side of road.

*** = BD 69-352
**** = Kaiminani Street (County Road)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

REFLECTOR MARKER SCHEDULE

QUEEN KA'AHUMANU HIGHWAY
GUARDRAIL AND SHOULDER IMPROVEMENTS
HAPUNA TOWARDS KAILUA-KONA
F.A. PROJECT NO. NH-019-1(31)

Scale: none
Date: April, 2001

SHEET No. 1 OF 1 SHEETS