

SECTION A-A

(@ Post #2)

PARTIAL VIEW OF POST 1

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HWY-H-02-01M	2001	24	24

ITEM NO.	QTY	BILL OF MATERIALS		
F3000	1	IMPACT HEAD		
F1303	1	W-BEAM GUARDRAIL END SECTION, 12 GA.		
F1304	1	W-BEAM GUARDRAIL CENTER SECTION, 12 GA.		
G1203	1	W-BEAM GUARDRAIL, 12 GA.		
<i>\$730</i>	2	*FOUNDATION SOIL TUBE, 6" x 8" x 72"		
E750	1	BEARING PLATE		
<i>S760</i>	1	CABLE ANCHOR BOX		
E770	1	BCT CABLE ANCHOR ASSEMBLY		
E780	1	GROUND STRUT		
PB620	2	STEEL BREAKAWAY END POST		
PB621	5	STEEL BREAKAWAY LINE POST		
	5	RECYCLED PLASTIC BLOCKOUT OR OFFSET BLOCK		
		HARDWARE		
B580122	25	5/8" Dia. x 1 1/4" SPLICE BOLT, POST #2		
B580754	2	5/8" Dia. x 7 1/2" HEX BOLT		
B341004	2	3/4" Dia. x 10" HEX BOLT		
B581002	5	5/8" Dia. x 10" H.G.R. BOLT (POST 3 THRU 7)		
N050	32	5/8" Dia. H.G.R. NUT (SPLICE 24, SOIL TUBES 2, POST 2 THRU 7, 6)		
N030	2	3/4" Dia. HEX NUT		
W050	6	H.G.R. WASHER		
W030	4	3/4" ID WASHER		
N100	2	1" ANCHOR CABLE HEX NUT		
W100	2	1" ANCHOR CABLE WASHER		
B140404	2	1/4" × 4" HEX BOLT		
N014	2	1/4" HEX NUT		
W014	4	1/4" WASHER		
SB58A	8	CABLE ANCHOR BOX SHOULDER BOLT		
N055A	8	1/2" A325 STRUCTURAL NUT		
W050A	16	1 1/16 OD x 9/18 ID A325 STR. WASHER		

Foundation Tube Options For Posts 1 & 2

*6'-0" Split Foundation Tubes S730 *6'-0" Solid Foundation Tubes E731

*5'-0" Foundation Tubes S735 W/Soil Plates SP600

*4'-6" Foundation Tubes E735 W/Soil Plates SP600



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

(Typical @ Post 3 - 7)

NOTE: RAIL NOT BOLTED @ POST #3

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION

FLEAT -350 FLARED ENERGY ABSORBING TERMINAL

HAWAII BELT ROAD **CULVERT REPAIRS AND RENOVATIONS VARIOUS LOCATIONS, HAWAII**

PROJECT NO. HWY-H-02-01M SCALE: AS NOTED **DATE: APRIL 27, 2001**

> SHEETS SHEET No. OF