

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-019-2(55)	2004	17	112

RECONSTRUCTION AREA SCHEDULE						
STATION		OFFSET FROM RD. C TO CENTER RECON. AREA (L.F.)		LENGTH (L.F.)	WIDTH (L.F.)	APPROX. AREA (SQ. FT.)
FROM	TO	LEFT	RIGHT			
13+46.80	68+40.71	6		5,494	12.5	68,675
68+41.60	97+50	6		2,908	12.5	36,350
0+00	57+31.07	6		5,731	12.5	71,638
155+25	169+15	6		1,390	12.5	17,375
54+53	55+29		6	76	13.5	1,026
74+08	74+88		6	80	13.5	1,080
75+30	75+48		6	18	13.5	243
76+12	77+25		6	113	13.5	1,526
77+25	77+76		6	51	13.5	689
77+88	78+44		6	56	13.5	756
TOTAL						199,358

BRIDGE APPROACH RECONSTRUCTION	
BRIDGE (Mauka Lane)	APPROX. AREA (SQ. FT.)
East Paauilo Bridge	1,300
Aamau Bridge	2,600
Kawaii Bridge	2,600
Kainehe Bridge	2,600
Kalapahapuu Bridge	2,600
Kukaiau Bridge	2,600
Mohuna Bridge	3,900
Kekualele Bridge	5,200
TOTAL	23,400

PAVEMENT RECONSTRUCTION	
Pay Item	Estimated Qty.
305.1000 Aggregate Subbase	4,125 C.Y.
306.1100 Untreated Permeable Base Course	4,125 C.Y.
312.0100 Plant Mix Glassphalt Concrete Base Course	12,310 Tons
651.1000 Exc. for Recon. of Weakened Pav't Areas	15,470 C.Y.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	4/04
No.	DESIGNED BY	4/04
	QUANTITIES BY	4/04
	CHECKED BY	4/04

CHAD M. McDONALD

LICENSED PROFESSIONAL ENGINEER

No. 9793-C

HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

Chad M. McDonald

MITSUNAGA & ASSOCIATES

STATE OF HAWAII

DEPARTMENT OF TRANSPORTATION

HIGHWAYS DIVISION

PAVEMENT RECONSTRUCTION SCHEDULE

HAWAII BELT ROAD RESURFACING

East Paauilo Bridge to Kaala Bridge

Federal Aid-Project No. NH-019-2(55)

Scale: As Noted

Date: April 2004

SHEET No. C-15 OF 49 SHEETS

17