

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	19L-01-22M	2022	2	5

GENERAL NOTES

1.

The project consists of cold planing, resurfacing, and reconstruction of existing pavement.

Reference attached County Plan and Profile sheets for the locations of the resurfacing limits. Resurface to the existing pavement grade. Disregard the proposed profile on the plans as well as callouts that are not related to resurfacing.
2.

The Contractor is reminded of the requirements of Subsection 105.16 - Subcontracts, which requires him to perform work amounting to not less than 30 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3.

The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.06 - Contractor Duty Regarding Public Convenience Subsection 104.11(A) - Contractor's Duty to Coordinate Utility Services, and Section 645 - Traffic Control.
4.

The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.
5.

At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
6.

The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
7.

The exact locations and limits or areas to be reconstructed and cold planed shall be determined in the field by the Engineer.
8.

Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, side streets and driveways as shown on the plans and/or as directed by the Engineer.
9.

Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.
10.

Contractor shall provide for access to and from existing side streets and driveways at all times.
11.

All saw cutting work shall be considered incidental to the various contract items.
12.

Unprotected pavement dropoffs greater than 2" shall not be allowed during non-working hours, except where approved by the Engineer in writing.
13.

Public Notice is required for lane closures. Contractor shall submit notice to the Engineer for approval a minimum of three (3) weeks prior to publication. Pre-approval of notice, with dates left blank, is permissible.

14.

The Contractor shall provide and maintain a temporary pedestrian-safe and easily accessible route or detour with barricades in or near the work zone. This temporary route or detour shall be stable, firm and slip-resistant and shall be Americans With Disabilities Act compliant. This work shall be incidental to all contract items and will not be paid for separately.
15.

Night work may be directed by the Engineer. All cost associated with night work shall be incidental to the contract items.

SURVEY PLOTTED BY	DATE	X
DRAWN BY		
DESIGNED BY		
NOTED BY		
QUANTITIES BY		
CHECKED BY		
ORIGINAL PLAN		
NOTE BOOK		
19L-01-22M		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

KALANIANA'OLE AVENUE
RECONSTRUCTION
KAMEHAMEHA AVENUE TO KAUHANE AVENUE
Project No. 19L-01-22M
Scale: Not To Scale Date: Jan., 2022

SHEET No. 1 OF 1 SHEETS