FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	130B-01-92	1997	60	115

REFLECTOR AND OBJECT MARKER SCHEDULE

STATION*		LEFT	RIGHT	RM-2BI	RM-2	RM-3 **			RM-3BI		RM-4	REMARKS
FROM	TO			FLEX POST	STEEL POST	STEEL BI	FLEX POST	NO POST	STEEL POST	FLEX POST	NO POST	
BYPASS												
73+00	— —	●	●	2								Drop Off
75+00	— —	●	●	2								Drop Off
77+00	— —	●	●	2								Drop Off
79+00	— —	●	●	2								Drop Off
81+00	— —	●	●	2								Drop Off
83+00	— —		●					2				Below D-11
84+00	— —	●		1								Drop Off
84+00	— —		●					1				Below R3-8
86+00	— —	●		1								Drop Off
86+00	— —		●					1				Below W3-3
88+00	— —	●	●	2								Drop Off
89+00	— —	●			1							End Guardrail
90+00	— —		●					1				Below M1-6(130)
91+50	— —		●				1					End Guardrail
92+00	— —	●						1				Below R2-1(45)
94+00	— —	●	●	2								Culvert
95+90	— —	●	●	2								Culvert
98+00	— —		●		1							Guardrail
99+40	— —		●				1					End Guardrail
99+60	— —	●					1					End Guardrail
100+00	— —	●	●	2								Drop Off
102+00	— —	●		1								Drop Off
102+00	— —		●					1				Below W9-2
102+50	— —		●				1					End Guardrail
105+00	— —		●				1					End Guardrail
105+20	— —		●	1								Culvert
105+80	— —	●		1								Culvert
110+60	— —		●					2				Below R2-1(45)
110+80	— —	●						1				End Guardrail
112+00	— —	●	●	2								Drop Off
114+00	— —	●	●	2								Drop Off
114+90	— —		●								2	Below R3-2
116+00	— —	●						2				Below R2-1(45)
116+00	— —		●	1								Drop Off
117+80	— —	●	●	2								Drop Off
BYPASS CONT.												
120+10	— —	●	●	2								Drop Off
122+00	— —	●	●	2								Drop Off
122+80	— —	●						2				Below R2-5b
ROAD "A"												
0+65	— —		●					1				Below W14-2
ROAD "B"												
4+60	— —	●					1					End Guardrail
8+00	— —	●						2				Below R1-1
EXIST. RTE. 130												
58+00	— —		●					1				Below R2-5b
59+50	— —	●						1				Below R2-5b
67+50	— —	●						1				Below W8-3
TOTALS				34	2	0	6	20			2	
ITEM NO.												

N.I.C.

NOTES:

1. Reflector markers located behind guardrail shall be installed with steelposts. At all other locations reflector markers shall be installed with flexible delineator posts.
2. Remove all existing reflector markers, object markers, and posts unless otherwise directed by the Engineer.
3. Removal of existing reflector markers, object markers, and posts shall be considered incidental to the various signing items.

* Stations may vary in the field
Final Marker locations are to be approved by the Engineer

** RM-3 to be installed on Sign Posts, as directed by the Engineer

NANCY E BURNS
LICENSED PROFESSIONAL ENGINEER
No. 6812-C
HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION.

Nancy E Burns

DATE: 8/8/97

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

BYPASS REFLECTOR AND OBJECT MARKER SCHEDULE

KEA'AU-PAHOA ROAD VICINITY OF KEA'AU TOWN (KEA'AU BYPASS ROAD)
PROJECT NO. 130B-01-92, PHASE 1

Scale: NA Date: May, 1997

SHEET No. 1 OF 1 SHEETS

ORIGINAL PLAN | SURVEY PLOTTED BY | DRAFT BY | TRACED BY | NOTE BOOK | DESIGNED BY | QUANTITIES BY | CHECKED BY | DATE

OBI-SCHdgn