

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	RS-0130(24)	2000	32	55

CENTERLINE & REFERENCE SURVEY MONUMENT SCHEDULE

PROJECT	STATION	MONUMENT TYPE	Adjust Centerline and Reference Mon. (ITEM NO. 613.0110)	Reconstruct Centerline and Reference Mon. (ITEM NO. 613.0120)	EXISTING DEPTH (FT.)
S-231(I)					
	59+87.16	P.C.	1		
	65+11.32	P.T.	1		
	76+22.05	P.C.	1		
	81+48.72	P.T.	1		
	93+66.72	P.C.	1		
	107+00.05	P.T.	1		
	109+78.55	P.C. Back (-2.24)	1		
	109+80.79	P.C. Ahead			
	112+32.04	R.O.W.	1		
	116+23.30	P.C.C.	1		
	120+51.97	P.T.	1		
	121+35.04	R.O.W.	1		
	127+69.98	P.C.	1		
	134+11.34	P.T.	1		
	161+97.09	P.C.	1		
	167+30.42	P.T.	1		
	182+62.71	P.C.	1		
	186+56.60	P.T.	1		
	198+81.95	P.C.	1		
	202+54.62	P.T.	1		
	221+39.15	P.C.	1		
	225+65.82	P.T.	1		
	237+50.00	EQ. STA.	1		
	0+00	EQ. STA.			
	5+87.77	P.C.	1		
	11+99.99	P.T.	1		
	17+04.57	P.C.	1		
	25+38.88	P.T.	1		
	TOTAL		26		

* DRIVEWAY SCHEDULE

STATION	TYPE	WIDTH(ft.)	LENGTH(FT.)	**AREA(SQ. FT.)
60+40 Lt.	A.C.	12.5	34	77
62+05 Lt.	A.C.	12.5	34	77
65+00 Lt.	A.C.	12.0	34	75
69+35 Lt.	Concrete	10.0	34	67
75+32 Rt.	A.C.	12.0	34	75
83+30 Rt.	A.C.	10.5	34	69
86+63 Rt.	A.C.	13.5	34	81
88+80 Lt.	A.C.	10.0	34	67
88+80 Rt.	A.C.	11.0	34	71
99+05 Rt.	Concrete	13.0	28	70
99+95 Lt.	Concrete	14.0	28	73
101+60 Lt.	Concrete	14.0	28	73
102+63 Rt.	A.C.	15.5	28	78
104+08 Rt.	A.C.	10.0	28	61
115+90 Rt.	A.C.	10.0	28	61
120+00 Rt.	A.C.	10.0	16	61

* Concrete driveways shall be paid for under Item No. 610.0100
A.C. driveways shall be paid for under Item No. 304.0100 and
Item No. 401.0500

**Includes radius corners

RELOCATED MAIL BOXES AND
NEWSPAPER DISPENSERS

STATION	TYPE
68+80 Lt.	Mailbox
69+20 Lt.	Newspaper Dispensers
83+20 Lt.	Mailbox
89+00 Lt.	Mailbox & Newspaper Dispenser (2)
89+00 Rt.	Newspaper Dispensers
99+10 Lt.	Mailbox
100+30 Lt.	Mailbox
TOTAL	8 Each

UTILITY SCHEDULE

STATION	FACILITY	ACTION	REMARKS
113+47 Rt.	Wooden Street Light Pole	Relocate	existing location to 113+55 and 40' offset
124+15 Rt.	Wooden Street Light Pole	Relocate	existing location to 124+30 and 40' offset
173+92 Lt.	Water Manhole	Reset	
173+92 Lt.	Water Manhole	Reset	
173+92 Lt.	Water Valve Box	Reset	
211+40 Rt.	Water Manhole	Reset	
211+40 Rt.	Water Manhole	Reset	
211+44 Lt.	Water Manhole	Reset	
211+65 Lt.	Water Manhole	Reset	
211+65 Lt.	Water Manhole	Reset	

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULES

KEA'AU-PĀHOA ROAD
PARADISE PARK SECTION-PHASE II & III
F.A. PROJECT NO. RS-0130(24)

Scale: None Date: May, 2000

SHEET No. 1 OF 2 SHEETS

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	X
4/17/00	CHECKED BY	
N. J. J.	QUANTITIES BY	
	CHECKED BY	

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	RS-0130(24)	2000	33	55

REFLECTOR AND OBJECT MARKER SCHEDULE

STATION		LEFT	RIGHT	RM-2 (White)		RM-3 (Yellow)			RM-3 (Bi-dir) (White)			RM-3 (Bi-dir) (Yellow)			RM-4		TYPE II	REMARKS
FROM	TO			STEEL POST	FLEX POST	STEEL POST	FLEX POST	W/OUT POST	STEEL POST	FLEX POST	W/OUT POST	STEEL POST	FLEX POST	W/OUT POST	STEEL POST	W/OUT POST	W/OUT POST	
71+25	—		●												1		Stop Sign, Aulii St,	
103+73	106+35	●			2		1			2							Guardrail Delineation	
105+10	—	●	●				2										Culvert	
106+35	—	●													1		Stop Sign, Makuu St.	
106+70	109+08	●			2		1			2							Guardrail Delineation	
113+93	118+68	●			4		2										Guardrail Delineation	
123+96	—		●												1		Stop Sign, Ainaloa St,	
127+31	134+68	●			6		2										Guardrail Delineation	
137+00	142+63	●			5		1										Guardrail Delineation	
147+46	—	●	●				2										Culvert	
164+00	173+63	●			9		1										Guardrail Delineation	
173+85	—	●													1		Stop Sign, Ka Ohuwalu St,	
204+23	210+88		●		6		2										Guardrail Delineation	
211+00	224+00	●			14										1		Drop off	
211+20	—	●													1		Stop Sign, Kaluahine St,	
211+83	—		●												1		Stop Sign, Ni' Aulani St.	
227+63	231+88	●			3		2										Guardrail Delineation	
Totals					51		16			4					7			

ROUTE MARKER SCHEDULE

ROUTE MARKER SCHEDULE							
PROJECT	STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE	INSTALL TYPE A ASSEMBLY	INSTALL TYPE B ASSEMBLY
S-23(1)							
	157+60	●		M1-6(130)			
	157+60		●	M1-6(130)			
	237+20	●		M1-6(130)			
	237+20		●	M1-6(130)			
TOTALS							

MILEPOST MARKER SCHEDULE

MILEPOST MARKER SCHEDULE						
PROJECT	STATION	LEFT	RIGHT	MILE POST * D10-5 (12"x36") MILE POST(RTE)	REMOVE	INSTALL WITH POST
S-23(I)	69+25		●	6(130)	1	1
	122+10		●	7(130)	1	1
	174+95		●	8(130)	1	1
	227+95		●	9(130)	1	1
TOTALS					4	4

* - *Bidirectional*

ORIGINAL PLAN	SURVEY PLOTTED BY _____	DATE _____
NOTE BOOK	DRAWN BY <u>X</u>	_____
<u>4prans2</u>	TRACED BY _____	_____
	DESIGNED BY <u>X</u>	_____
	QUANTITIES BY _____	_____
	CHECKED BY _____	_____
	Ss. <u>dgn</u>	_____

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULES

KEA'AU-PĀHOA ROAD
PARADISE PARK SECTION-PHASE II & III
F.A. PROJECT NO. RS-0130(24)

Scale: None Date: May, 2000