NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL NOTES

- (A) Erosion and Sediment Control Inspection and Maintenance Practices.
 - (1) The Contractor shall inspect the erosion and sediment control measures at least once a week or after 0.5 inches of rainfall.
 - (2) The Contractor shall maintain the erosion and sediment control measures according to the contract. If a repair is necessary, the Contractor shall initiate the repairs within twenty-four (24) hours after the inspection such
 - (a) When sediment build-up reaches one-third (1/3) the height of the silt fence, the Contractor shall remove and dispose of the sediment build-up from the silt fence.
 - (b) When the depth of the sediment basin reaches ten percent (10%) of the design capacity, the Contractor shall remove and dispose of the sediment build-up.
 - (c) When tears are found on the silt fence, the Contractor shall replace the fabric.
 - (d) The Contractor shall check to see if the fabric is securely attached to the fence posts and to see that the fence posts are firmly in the ground.
 - (e) The Contractor shall inspect the diversion dike and repair the breaches.
 - (f) The Contractor shall inspect temporary and permanent seeding and planting for bare spots, washouts, and healthy growth.
 - (3) The Contractor shall have its personnel make a maintenance inspection report promptly after each inspection. The Contractor shall select a minimum of three (3) personnel who will be responsible for inspection, maintenance, repair activities, and filling out the inspection and maintenance report. Personnel selected for the inspection and maintenance responsibilities will receive training from the Contractor. The Contractor shall train these personnel in the inspection and maintenance practices necessary for keeping the erosion and sediment used onsite according to the contract.
- (B) No construction activities will be authorized until the Contractor's Site-Specific BMP has been approved by the Highways Division.

FED. ROAD DIST.

STATE FED. AID PROJ. NO.

FISCAL SHEET NO.

SHEETS

HAWAI'I HAW. RS-0130(24) 2000 9 55

STATE OF HAWAI'I
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

NPDES GENERAL NOTES

<u>KEA'AU-PĀHOA ROAD</u>

PARADISE PARK SECTION-PHASE II \$ III

F.A. PROJECT NO. RS-0130(24)

Scale: None

Date: May, 2000

SHEET No. 1 OF 1 SHEETS