

1 **SECTION 407 – TACK COAT**
2

3 Make the following amendments to said Section:
4

5 **(I)** Amend **Subsection 407.03(D) — Application of Tack Coat** by revising lines 63-
6 68 to read:

7
8 “Apply tack coat on existing asphalt pavement or concrete surface, or both,
9 to be overlayed by HMA course. Once water has evaporated from asphalt
10 emulsion, tack coat is said to have set. Place HMA overlay after tack coat
11 has set and within four hours of application. For multiple lift construction,
12 tack coat application will not be waived. Remove all deleterious material to
13 bonding before applying the tack coat.”
14

15 **(II)** Amend **Subsection 407.03(D) — Application of Tack Coat** by adding the
16 following after line 72:

17
18 “Apply tack coat on all surfaces that will have an asphalt pavement placed
19 on it in an uniform, full coverage manner, e.g., no visible streaks, holidays
20 in the application, no differences in the application rate, i.e., thickness of the
21 tack coat. The exception to this requirement shall be surfaces that will have
22 pavement joint adhesive applied to it.”
23
24
25

26 **END OF SECTION 407**