

1 Make the following section a part of the Standard Specifications:

2
3 **“SECTION 627 – BOLT DOWN CURB WITH DELINEATORS**

4
5 **627.01 Description.** This section describes furnishing and installing bolt down
6 curb with delineators shown in the plans according to the requirements of the
7 contract or as ordered by the Engineer.

8
9 **627.02 Materials.** The bolt down curb with delineators system shall consist of a
10 prequalified product such as Tuff Curb or approved equal.

11
12 Tuff Curb is NCHRP is a MASH compliant product if used as tested. The
13 test used a nose piece so application should use a nose piece.

14
15 System shall be of uniform composition, free from surface irregularities, and
16 free from other physical damage or defects that affect appearance or performance,
17 or both.

18
19 **627.03 Construction.** Contractor shall furnish and install bolt down curb with
20 delineators system per manufacturer's specifications at locations identified on
21 plans.

22
23 **(A) General.**

24
25 **(1)** Remove surface moisture and other materials that may
26 adversely affect system installation.

27
28 **(2)** Establish control points and layout alignment for bolt down
29 curb system.

30
31 **(3)** Spacing between curb sections shall be 12” to allow for
32 drainage.

33
34 **(4)** Bolt down curb should begin and end with corresponding end
35 sections per manufacturer's specifications.

36
37 **627.04 Measurement.** The Engineer will measure bolt down curb with
38 delineators system per linear foot in accordance with the contract documents.
39 Longitudinal gaps for gaps 10 feet or less will be included in the measurement.

40
41 **627.05 Payment.**

42
43 The Engineer will pay for the following pay items when included in the
44 proposal schedule:

45
46

Pay Item	Pay Unit
Bolt Down Curb with Delineators (incl. Nose Pieces)	Linear Foot”

47
48
49 **END OF SECTION 627**

STP-0130(27)

627-1a

09/01/20