

1       **SECTION 638 – PORTLAND CEMENT CONCRETE CURB AND GUTTER**

2  
3       Make the following amendments to said Section:

4  
5       **(I)**       Amend **638.04 – Measurement** by revising lines 130 to 131 to read as  
6       follows:

7  
8       **“638.04 Measurement.** The Engineer will measure curb and/or gutter, both new  
9       and reset, by the linear foot. The Engineer will measure along the front face of the  
10      curb at the finished grade elevation. If the Engineer measures gutter separately,  
11      the Engineer will measure gutter along the front face of the gutter. The Engineer  
12      will not make deduction in gutter length for drainage appurtenances installed such  
13      as catch basins and drop inlets.  
14

15       The Engineer will measure curb and/or gutter transition for payment as  
16      follows:  
17

From	To	Measurement for Payment
Cast-in-place Curb or Precast Curb	Cast-in-place Curb and Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter	Precast Curb and Cast-in-place Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter Mountable	Cast-in-place Curb and Gutter Mountable	Cast-in-place Curb and Gutter 1/2 of Transition to each type

18  
19       The Engineer will measure precast concrete drop curb and driveway curb  
20      or cast-in-place integral driveway curb and gutter under the adjacent normal curb  
21      and/or gutter.”  
22

23       **(III)**       Amend **638.05 – Payment** by revising lines 133 to 148 to read as follows:

24  
25       **“638.05 Payment.** The Engineer will pay for the accepted quantities of curb  
26      and/or gutter at the contract unit price per linear foot for each type of curb and/or  
27      gutter specified.  
28

29       Payment will be full compensation for work prescribed in this section and  
30      contract documents.  
31

