FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190E-01-98M	1998	19	30

STRIPING AND PAVEMENT MARKING SCHEDULE

Station	Traffic Regime		Thermoplastic or Tape type ( ) (linear feet)																Pavement Markers (each)				
	Lt	Rt	629.1020 4" Double Yellow (I)	4" Double Yellow Guidelines (I)	629.1011 4" Yellow C.L. (I)	12" Yellow Diagonal (II)	4" White Stripe (I)	629.1012 4" White E.P. (II)	8" White Stripe (I)	629.1013 8" White Stripe (II)	12" White Diagonal (II)	4" White Edge Line Extension (III)	4" White Guide Lines (III)	629.1017 12" Stop Bar (III)	Solid White Arrow Rt. (III)	Solid White Arrow St. (III)	Solid White Arrow Lt. (III)	Solid White Words (III)	629.2010 A	629.2030 C	629.2040 D	629.2050 H	629.2060 J
431+50	NP	NP	105					210												6	6		
430+45								10												1			
OPEN								10												1			
430+25	P	NP			530			1,060												26	13	13	56
424+95	P	P						3,180												80	40		156
409+05	NP	P			920			1,840												40	22	22	88
399+85	NP	NP	685					1,370												34	34		
393+00								20												1			
OPEN								20												1			
392+60	NP	NP	6,870					13,740												344	344		
323+90	NP	P			910			1,820												46	23	22	88
314+80	NP	NP	4,550					9,100												228	228		
269+10	P	NP			920			1,840												46	23	22	88
259+90	P	P						3,378												84	42		172
243+01	P	P								1,002										26	13		52
238+00	NP	NP	269							498										14	14		
235+51	NP	NP	271							542										14	14		
232+80																							
LALAMILO RD.	NP	NP	80					172						22						6	6		
AIRPORT RD.	NP	NP	100					200						24						10	10		
	TOTALS		12,910		3,280			37,970		2,042				46						1,008	832	79	700

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
NOTE BOOK	TRACED BY	
	DESIGNED BY	
No.	QUANTITIES BY	
	CHECKED BY	

GORDON Y. IMATA LICENSED PROFESSIONAL ENGINEER No. 2726-C HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRIPING AND PAVEMENT MARKING SCHEDULE

MAMALAHOA HIGHWAY RESURFACING
WAIMEA TO KAMAKOA BRIDGE NO. 1
PROJECT NO. 190E-01-98M

Scale: As Shown Date: April, 1998

SHEET No. 1 OF 1 SHEETS