
FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190E-01-98M	1998	25	30

	RL	EFL	EC	TOR	AND	OBJE	CT MA	ARKER	R SCH	HEDUL	E (C	ontinu	ed)
STATION*		FT	HT	RM-2		RM-3 **		RM−3 (Bi)		RM-4			
FROM	ТО	LEFT	RIGHT	STEEL POST	STEEL Bl	FLEX POST	STEEL POST	NO POST	STEEL POST	FLEX POST	STEEL POST	NO POST	REMARKS
435+50	238+00	•	•					<i>52</i>					ON SIGN POSTS
430+70	430+40	•		3									SIDEROAD CURVE
410+36	400+42		•				,					7	ON TELEPHONE POLES
398+17		•										1	ON TELEPHONE POLE
395+89		•	•									2	ON GUY POLE ON TELEPHONE POLE
399+00	397+80			3									
393+02		•			·							1	ON TELEPHONE POLE
382+58	377+51	•		5									
359+00	354+00	•		6									
359+00	354+00		•	6									
310+50	307+50	•		5									
304+60	302+20			4									
293+00	291+00		•	3									
287+00	284+60	•		4									
279+00	277+00		•	3									
236+30	235+90								2				BEHIND GUARD RAIL
236+20	235+65								3				BEHIND GUARD RAIL
235+51	235+31	•									4		AT BRIDGE END POST
243+20		•							2				AT CULVERT
	TOTALS			42				52	7		4	11	

<sup>\*</sup> Stations may vary in the field. Final Marker locations are to be approved by the Engineer.



STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

REFLECTOR AND OBJECT

MARKER SCHEDULE

MAMALAHOA HIGHWAY RESURFACING WAIMEA TO KAMAKOA BRIDGE NO. 1

Project No. 190E—01—98M
Scale: None Date: April, 1998

SHEET No. 1 OF 1 SHEETS

<sup>\*\*</sup> RM-3 to be installed on Sign Posts, as directed by the Engineer.