

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190DE-01-99M	1999	49	50

CENTERLINE AND REFERENCE SURVEY MONUMENT SCHEDULE				
STATION	MONUMENT TYPE	ADJUST AND/OR RECONSTRUCT EXIST. ITEM NO. 613.0110	CENTERLINE OFFSET * (FT.)	EXIST. DEPTH (FT.)
208+84.61	P.C. Mon.	X		
223+81.28	P.T. Mon.	X		
241+54.80	P.C. Mon.	X		
<del>253+70.36</del>	<del>P.T. Mon.</del>	<del>X</del>		
259+99.88	T.S. Mon.	X		
263+61.21	C.S. Mon.	X		
41+67.43	P.C. Mon.	X		
79+98.38	P.C. Mon.	X		
83+04.16	P.T. Mon.	X		
TOTALS		<del>9</del> 9		

\* Right and Left Stations Are Determined When Facing in the Up Station Direction

MILEPOST AND ROUTE MARKER SCHEDULE					
STATION	LEFT	RIGHT	ROUTE MARKER SIGN NO. (ROUTE NO.)	REMOVE	INSTALL WITH POST (ASSEMBLY TYPE)
147+50		●	M1-6 (200)	X	X (A)
150+26	●		M1-6 (190)	X	X (A)
150+94		●	M1-6 (190)	X	X (B)
150+94		●	M1-6 (200)	X	X (B)
153+50	●		M1-6 (190)	X	X (B)
153+50	●		M1-6 (200)	X	X (B)
156+80	✓●^	●	M1-6 <del>190</del> (190)	X	X (A)
157+50	●	✓●^	M1-6 <del>190</del> (200)	X	X (A)
TOTALS				8	8
STATION	LEFT	RIGHT	MILE POST D10-4 (MILE) W/D10-7 (ROUTE NO.)	REMOVE	INSTALL WITH POST (BI-DIRECTIONAL)
237+00	●		9 (190)	X	X
59+60	●		8 (190)	X	X
<del>112+47</del>	●		7 (190)	X	X
<del>112+44</del>					
165+60	●		6 (190)	X	X
218+20	●		5 (190)	X	X
			TOTALS	5	5

\* Contractor Shall Submit Shop Drawings of Mile Post Sign to the Engineer for Approval Prior to Fabrication.

LEGEND FOR AS-BUILT POSTINGS	
~~~~~	Squiggly line for as-built deletion
<del>100-00</del>	Double line for as-built deletion
Roadway	Text for as-built posting

6/3/99 Revised Description for Item No. 613.0110, Deleted Column for Reconstruct Exist. Item No. 613.0120.

Date Revision

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

MISCELLANEOUS SCHEDULES

MAMALAHOA HIGHWAY RESURFACING  
Vicinity of Kamakoa Bridge No. 1 to Keamoku  
Project No. 190DE-01-99M

Scale: As Shown Date: June, 1999

SHEET No. 1 OF 1 SHEETS

"AS-BUILT"

ADD. 49