

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190BC-01-05M	2005	11	13

STRIPING AND PAVEMENT MARKING SCHEDULE

HWY. SECTION	STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION			PAVEMENT MARKERS (EACH)			
	FROM	TO	NORTH BOUND LANE (LEFT)	SOUTH BOUND LANE (RIGHT)	4"Double Yellow Item No. 629.1018	4"Single Yellow Item No. 629.1011	4"Single White Item No. 629.1013	C Item No. 629.2030	D Item No. 629.2040	H Item No. 629.2070	J Item No. 629.2080
190 C	End Project - Sta. 642+00, 16.45 Milepost (match to existing striping)										
	608+34	642+00	N	N	3,366		6,732	168	168		
	608+26	608+34	Equation Station								
	591+64	608+26	N	N	1,662		3,324	84	84		
	591+53	591+64	Equation Station								
	574+30	591+53	N	N	1,723		3,446	88	88		
	565+50	574+30	P	N		880	1,760	44	22	22	88
	560+40	565+50	P	P			1,020	26	13		48
	553+10	560+40	N	P		730	1,460	36	18	19	76
	551+60	553+10	P	P			300	8	4		12
	543+95	551+60	P	N		765	1,530	40	20	19	76
	534+80	543+95	N	P		915	1,830	48	24	22	88
	495+50	534+80	N	N	3,930		7,860	8	8		
	486+00	495+50	P	N		950	1,900	48	24	23	92
	475+90	486+00	N	N	1,010		2,020	52	52		
	466+75	475+90	P	N		915	1,830	48	24	22	88
	457+60	466+75	N	P		915	1,830	48	24	22	88
	456+27	457+60	N	N	133		266	8	8		
	OPEN		Big Island Country Club, Sideroad Left				120	6	5		
	449+00	455+87	N	N	687		1,374	34	34		
	448+50	449+00	Equation Station								
	441+20	448+50	N	N	730		1,460	36	36		
	OPEN		Puu Lani Ranch, Sideroad Right				120	6	5		
	435+65	440+75	N	N	510		1,020	26	26		
	OPEN		Big Island Country Club, Sideroad Left				100	4	3		
	422+28	435+25	N	N	1297		2,594	66	66		
	421+66	422+28	Equation Station								
	407+57	421+66	N	N	1409		2,818	70	70		
	407+62	407+57	Equation Station								
	381+65	407+62	N	N	2,597		5,194	130	130		
	OPEN		Puu Waawaa Ranch, Sideroad Right				120	6	5		
	380+50	381+20	N	N	70		140	6	6		

STRIPING AND PAVEMENT MARKING SCHEDULE

HWY. SECTION	STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION			PAVEMENT MARKERS (EACH)			
	FROM	TO	NORTH BOUND LANE (LEFT)	SOUTH BOUND LANE (RIGHT)	4"Double Yellow Item No. 629.1018	4"Single Yellow Item No. 629.1011	4"Single White Item No. 629.1013	C Item No. 629.2030	D Item No. 629.2040	H Item No. 629.2070	J Item No. 629.2080
190 B	375+50	380+50	N	N	500		1,000	26	26		
	366+30	375+50	P	N		920	1,840	46	23	23	92
	357+74	366+30	P	P			1,712	44	22		88
	357+32	357+74	Equation Station								
	356+40	357+32	P	P			184	6	3		12
	347+30	356+40	N	P		910	1,820	46	23	23	92
	306+00	347+30	N	N	4,130		8,260	208	208		
	296+80	306+00	P	N		920	1,840	46	23	23	92
	294+50	296+80	P	N		230	460	12	6	6	24
	288+00	294+50	N	P		650	1,300	34	17	18	72
	285+30	288+00	P	P			540	14	7		28
	278+80	285+30	P	N		650	1,300	34	17	18	72
	265+30	278+80	P	P			2,700	68	34		
	256+10	265+30	N	P		920	1,840	46	23	23	92
	255+50	256+10	N	N	60		120	4	4		
	255+33	255+50	Equation Station								
	223+60	255+33	N	N	3,173		6,346	160	160		
	215+20	223+60	P	N		840	1,680	42	21	21	84
	207+30	215+20	P	P			1,580	40	20		80
	205+60	207+30	N	P		170	340	10	5	6	24
	198+10	205+60	P	P			1,500	38	19		76
	196+80	198+10	P	N		130	260	8	4	5	20
	180+10	196+80	P	P			3,340	84	42		168
	173+17	180+10	N	P		693	1,386	36	18	18	72
	173+18	173+17	Equation Station								

(Continued)

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
STRIPING AND PAVEMENT MARKING SCHEDULE
MAMALAHOA HIGHWAY, ROUTE 190 PAVEMENT REPAIRS - KA'UPULEHU TO PU'U'ANAHULU
PROJECT NO. 190BC-01-05M
Scale: As Shown Date: April, 2005
SHEET No. 1 OF 2 SHEETS

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190BC-01-05M	2005	12	13

STRIPING AND PAVEMENT MARKING SCHEDULE											
HWY. SECTION	STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION			PAVEMENT MARKERS (EACH)			
	FROM	TO	NORTH BOUND LANE (LEFT)	SOUTH BOUND LANE (RIGHT)	4"Double Yellow Item No. 629.1018	4"Single Yellow Item No. 629.1011	4"Single White Item No. 629.1013	C Item No. 629.2030	D Item No. 629.2040	H Item No. 629.2070	J Item No. 629.2080
190 B	173+00	173+18	N	P		18	36	2	1	1	4
	171+10	173+00	P	P			380	10	5		20
	163+80	171+10	P	N		730	1,460	36	18	18	72
	138+30	163+80	P	P			5,100	128	64		256
	129+50	138+30	N	P		880	1,760	44	22	22	88
	124+62	129+50	N	N	488		976	24	24		
	124+28	124+62	Equation Station								
	120+80	124+28	N	N	348		696	18	18		
	111+70	120+80	N	P		910	1,820	46	23	22	88
	82+94	111+70	N	N	2,876		5,752	144	144		
	82+19	82+94	Equation Station								
	49+50	82+19	N	N	3,269		6,538	164	164		
	Begin Project - Sta. 49+50, 27.63 Milepost (match to existing striping)										
TOTALS					33,968	15,641	118,034	3,000	2,365	396	2,372

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DESIGNED BY	
QUANTITIES BY	CHECKED BY	
NAME		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

STRIPING AND PAVEMENT
MARKING SCHEDULE

MAMALAHOA HIGHWAY, ROUTE 190 PAVEMENT
REPAIRS - KA'UPULEHU TO PU'UANAHULU
PROJECT NO. 190BC-01-05M

Scale: As Shown Date: April, 2005

SHEET No. 2 OF 2 SHEETS