

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190B-02-04M	2006	27	30

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE										
STATION	LEFT	RIGHT	TYPE	APPROX. M.P.	REMOVE	INSTALL (10 SQ. FT. OR LESS)		INSTALL (GREATER THAN 10 SQ. FT.)		REMARKS
						W/POST	W/O POST	W/POST	W/O POST	
52+20	X		W1-5 (36" x 36")		1	1				
53+00	X		"SCENIC POINT"		1			1		36" x 78"
75+32		X	"ADOPT A HIGHWAY LITTER CONTROL NEXT 2 MILES"		1			1		
110+10	X		R2-4 (40) (24" x 30")		1					
113+25	X		R2-1 (55) (24" x 30")		1					
113+25	X		R2-4a (50) (40) (36" x 72")					1		
113+25		X	R2-1 (55) (24" x 30")		1					
113+25		X	R2-4a (50) (40) (36" x 72")					1		
119+10		X	R2-4 (40) (24" x 30")		1					
125+10		X	W1-2R (36" x 36")		1	1				
133+95	X		W1-2L (36" x 36")		1	1				
187+55		X	"ADOPT A HIGHWAY LITTER CONTROL NEXT 2 MILES"		1			1		
187+80	X		"ADOPT A HIGHWAY LITTER CONTROL NEXT 2 MILES"		1			1		
296+30	X		"ADOPT A HIGHWAY LITTER CONTROL NEXT 2 MILES"		1			1		
297+15		X	"ADOPT A HIGHWAY LITTER CONTROL NEXT 2 MILES"		1			1		
339+90		X	W1-2L (36" x 36")		1	1				
352+95	X		W1-2R (36" x 36")		1	1				
369+50		X	W1-2R (36" x 36")		1	1				
371+76	X		"BUCKLE UP IT'S THE LAW"		1	1		1		
371+76		X	"BUCKLE UP IT'S THE LAW"		1	1		1		
378+00		X	W3-5 (35) (48" x 48")					1		
379+45	X		W1-2L (36" x 36")		1	1				
*49+50	X		R2-1 (35) (24" x 30")	35.17	1					
*49+50	X		R2-1-A (35) (36" x 48")	35.17				1		
*62+00		X	R2-1-A (45) (36" x 48")	34.93				1		Across exist. Speed Limit (35) sign
*62+50		X	R2-1 (45) (24" x 30")	34.93	1					
*67+00	X		R2-5b (35) (24" x 40")	34.84	1					
*67+00	X		W3-5 (35) (48" x 48")	34.84				1		
*94+00		X	R2-1 (45) (24" x 30")	34.33	1					
*94+00		X	R2-1-A (45) (36" x 48")	34.33				1		
*99+50	X		R2-1 (45) (24" x 30")	34.23	1					
*99+50	X		R2-1-A (45) (36" x 48")	34.23				1		
*142+50	X		R2-1 (45) (24" x 30")	33.41	1					
*142+50	X		R2-1-A (45) (36" x 48")	33.41				1		
*155+00		X	R2-1 (45) (24" x 30")	33.18	1					
*155+00		X	R2-1-A (45) (36" x 48")	33.18				1		
*210+00	X		R2-1 (45) (24" x 30")	32.13	1					
*210+00		X	R2-1 (55) (24" x 30")	32.13	1					
*211+30	X		R2-1-A (45) (36" x 48")	32.10				1		
*211+30		X	R2-1-A (50) (36" x 48")	32.10				1		Locate at edge or GRP wall
*215+00	X		R2-5b (35) (24" x 40")	32.03	1					
*216+30	X		W3-5 (45) (48" x 48")	32.01				1		
			TOTALS		29	9 7		9 21		
CONTRACT ITEM NUMBER						621B.5100		621B.5300		

* These signs are outside of the project limits but need to be installed / replaced.

MILEPOST MARKER SCHEDULE				
STATION	LEFT	RIGHT	MILE POST D10-2 (10"x27") MILE POST NO. (RTE. NO.)	INSTALL WITH POST (Bi-Dir)
76+49.77	X		27 (190)	1
136+81.87	X		26 (190)	1
189+02.31	X		25 (190)	1
241+74.22	X		24 (190)	1
296+87.25	X		23 (190) / 37 KI	1
347+34.39	X		22 (190)	1
CONTRACT ITEM NO. 621C.7610			TOTALS	6

Sheet Title: SIGN REPLACEMENT SCHEDULE
Last Save by: RGQ
Last Saved: 4/13/2006
Plotted on: 5/4/2006
G:\DOT\H04-02\ACAD\ROUTE190\dwg\Sheets\DOT40227.dwg

DESIGNED BY	DATE
DRAWN BY	
CHECKED BY	
APPROVED BY	
NOTED BY	
ORIGINAL PLAN	

RYAN G. QUITORIANO

LICENSED PROFESSIONAL ENGINEER

No.11122-C

HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

Expiration Date of the License: 04/30/08

STATE OF HAWAII

DEPARTMENT OF TRANSPORTATION

HIGHWAYS DIVISION

SIGN REPLACEMENT SCHEDULE

MAMALAHOA HIGHWAY PAVEMENT PREVENTIVE MAINTENANCE

Puu Waawaa Ranch to Kaupulehu

Project No. 190B-02-04M

Scale: As Shown

Date: April 2006

SHEET NO. 1 OF 1 SHEETS