

Sheet Title: STRIPING AND PAVEMENT MARKING SCHEDULE
Last Save by: RGQ
Last Saved: 4/13/2006
Plotted on: 5/4/2006
G:\DOT\04-02\ACAD\ROUTE190\dwg\Sheets\DOT40226.dwg

ORIGINAL PLAN	DESIGNED BY	DATE
	STRIPPED BY	
	DESIGNED BY	
	STRIPPED BY	
NOTEBOOK	QUANTITIES BY	
	CHECKED BY	
No.		

STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION (lin. ft.)			PAVEMENT MARKERS			
FROM	TO	LEFT	RIGHT	4" Double Yellow	4" Yellow	4" White E.P. Stripe	C	D	H	J
49+50	51+43	N	P		193	386	10	5	5	20
51+43	55+45	N	N	402		804	20	21		
55+45	61+45	P	N	600		1,200	30	15	14	56
61+45	82+19	N	N	2,074		4,149	104	104		
	82+94									
82+19	100+00	N	N	1,706		3,412	86	86		
82+94										
100+00	106+70	N	P		670	1,340	34	17	16	64
106+70	109+00	N	N	230		460	12	12		
109+00	111+80	P	N		280	560	14	7	8	32
111+80	115+55	P	P			750	20	10		36
115+55	120+79	N	P		524	1,048	28	14	13	52
120+79	124+28	P	N		349	698	20	10	8	32
	124+62									
124+28	128+41	P	N		380	759	20	10	8	32
124+62	128+41									
128+41	129+45	P	N		104	208	8	4	2	8
128+41										
129+45	130+85	N	P		140	280	8	4	2	8
	130+85									
130+85	138+25	N	P		740	1,481	36	18	19	76
130+85										
138+25	164+13	P	P			5,176	128	64		256
164+13	171+00	P	N		687	1,374	34	17	18	72
171+00	171+30	P	P			61	2	1		
	171+30									
171+30	173+18	P	P			375	10	5		16
171+30	173+17									
173+18	173+28	P	P			22	2	1		
173+17										
173+28	180+18	N	P		690	1,380	34	17	18	72
180+18	196+86	P	P			3,336	84	42		164
196+86	198+16	P	N		130	260	6	3	4	16
198+16	205+66	P	P			1,500	38	19		72
205+66	207+36	N	P		170	340	8	4	5	20
207+36	215+25	P	P			1,578	40	20		76
215+25	223+54	P	N		829	1,658	42	21	21	84
223+54	224+65	N	N	111		222	6	6		
224+65	230+10	N	P		545	1,090	28	14	13	52
230+10	232+78	N	N	268		536	14	14		
232+78	238+65	P	N		587	1,174	30	15	14	56
238+65	239+15	N	N	50		100	4	3		
239+15	245+83	N	P		668	1,336	34	17	16	64
245+83	247+51	N	N	168		336	8	9		
247+51	254+15	P	N		664	1,328	34	17	16	64
254+15	255+33	N	N	118		236	6	6		
	255+50									
255+33	256+00	N	N	50		101	4	3		
255+50										
256+00	265+01	N	P		901	1,802	44	22	23	92
265+01	278+82	P	P			2,762	70	35		136
278+82	284+90	P	N		608	1,216	30	15	16	64

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	190B-02-04M	2006	26	30

STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION (lin. ft.)			PAVEMENT MARKERS			
FROM	TO	LEFT	RIGHT	4" Double Yellow	4" Yellow	4" White E.P. Stripe	C	D	H	J
284+90	287+99	P	P			618	16	8		28
287+99	294+07	N	P		608	1,216	30	15	16	64
294+07	296+74	P	P			534	14	7		24
296+74	303+65	P	N		691	1,382	34	17	18	72
303+65	305+52	P	P			374	10	5		16
305+52	309+11	N	P		359	718	18	9	9	36
309+11	312+00	N	N	289		578	20	20		
312+00	316+36	P	N		436	872	22	11	12	48
316+36	318+23	P	P			374	10	5		16
318+23	321+02	N	P		279	558	14	7	7	28
321+02	324+72	N	N	370		740	20	19		
324+72	329+14	P	N		442	884	22	11	12	48
329+14	330+18	P	P			208	6	3		8
330+18	334+64	N	P		446	892	22	11	11	44
334+64	337+94	N	N	330		660	18	17		
337+94	343+04	P	N		510	1,020	26	13	12	48
343+04	347+29	N	N	425		850	22	22		
347+29	356+46	N	P		917	1,834	46	23	24	96
356+46	357+32	P	P			173	4	2		4
	357+74									
357+32	366+31	P	P			1,713	44	22		84
357+74										
366+31	375+46	P	N		915	1,830	46	23	23	92
375+46	380+50	N	N	504		1,008	26	26		
TOTAL				7,696	15,462	65,868	1,680	1023	403	2548
CONTRACT ITEM NO.				629.1020	629.1011	629.1011	629.2030	629.2040	629.2070	629.2091

Note:
Eradicate existing pavement markings and install new.

RYAN G. QUITORIANO

LICENSED PROFESSIONAL ENGINEER

No.11122-C

HAWAII, U.S.A.

THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION

Expiration Date of the License 04/30/08

STATE OF HAWAII

DEPARTMENT OF TRANSPORTATION

HIGHWAYS DIVISION

STRIPING AND PAVEMENT MARKING SCHEDULE

MAMALAHOA HIGHWAY PAVEMENT PREVENTIVE MAINTENANCE

Puu Waawaa Ranch to Kaupulehu

Project No. 190B-02-04M

Scale: As Shown

Date: April 2006

SHEET NO. 1 OF 1 SHEETS