

PTA MISCELLANEOUS SUMMARIES (1 of 2)												REG	STATE	PROJECT	SHEET NO.	TOTAL SHEETS
												9	HI	HI A-AD-6(2) Saddle Road	C8	C10
EROSION CONTROL & SLOPE PROTECTION									EARTH BERM			MISC				
Item Number			15702AA	15703	15709	15735	62504B	62504BBFM	62901C	15706	25101A	***	62404N	20101	21101	
Station to Station			Temporary Soil Tackifier* (acre) - for Roadway Protection	Silt Fence (linear foot)	Check Dams** (each)	Sediment Control Log (each)	Mulching Hydraulic Method (acre)	Mulching Hydraulic Method, Bonded Fiber Matrix (acre)	Erosion Control Mat, Type 3 (square yard)	Earth Berm (linear foot)	Placed Riprap, Class 1 (cubic yard)	Earthwork Geotextile, Type IV-E (square yard)	Placing Conserved Topsoil, 6-Inch Depth (square yard)	Clearing and Grubbing (acre)	Roadway Obliteration (square yard)	
88+00	to	92+00	0.60	500	4	0	0.41	0.36	0	100	12	81	3531	1.33	0	
92+00	to	98+00	1.08	50	38	0	0.40	0.73	0	800	96	644	5050	2.11	71	
98+00	to	111+00	2.37	0	24	0	0.89	1.27	8996	1300	156	1047	14763	5.42	0	
111+00	to	126+00	2.25	1500	0	39	1.76	0.00	5329	550	66	443	12520	4.84	0	
126+00	to	135+00	1.60	150	0	0	1.06	0.00	2951	900	108	725	5793	2.75	224	
135+00	to	165+00	4.48	3000	6	69	4.01	0.00	521	650	78	524	19198	8.44	0	
165+00	to	173+00	1.46	0	21	0	0.97	0.00	0	800	96	644	4607	2.41	0	
173+00	to	191+50	2.71	1850	3	40	2.21	0.00	0	200	24	161	10487	4.86	78	
191+50	to	199+00	1.33	150	18	0	1.06	0.00	0	750	90	604	5040	2.12	1244	
199+00	to	206+00	1.04	400	3	24	1.30	0.00	758	150	18	121	6842	1.98	2304	
206+00	to	209+50	0.60	200	17	0	0.23	0.00	609	350	42	282	1642	0.94	0	
209+50	to	213+50	0.60	400	3	12	0.48	0.00	0	100	12	81	2290	1.07	0	
213+50	to	217+00	0.57	350	12	0	0.35	0.00	0	350	42	282	1632	0.91	0	
217+00	to	221+00	0.62	400	7	0	0.34	0.00	0	200	24	161	1619	0.95	0	
221+00	to	223+00	0.29	200	0	27	0.37	0.00	0	0	0	0	1719	0.64	0	
223+00	to	227+00	0.59	400	1	10	0.49	0.00	0	50	6	40	2312	1.06	48	
227+00	to	231+00	0.63	400	4	0	0.44	0.00	0	250	30	201	2076	1.06	88	
231+00	to	242+00	1.66	1100	5	14	1.58	0.00	0	200	24	161	7491	3.08	582	
242+00	to	249+00	1.27	50	19	0	0.92	0.00	0	700	84	564	4344	2.17	0	
249+00	to	258+50	1.42	950	9	24	0.99	0.00	0	300	36	242	4695	2.39	0	
SCHEDULE A TOTAL			21.1	9400	119	221	16.0	1.3	19164	6600	794	5317	92540	39.5	3986	
SCHEDULE B TOTAL			27.2	12050	194	259	20.3	2.4	19164	8700	1047	7008	117651	50.5	4639	
*Add 0.93 acre (Schedule A), and 0.20 acre (Schedule B) to totals for waste stockpile protection.																
**Check dams may be sediment control log types or other approved by the CO.																
***For Information Only.																

M:\Mproj\Lennie\203027\100%summaries\pta-phase2.xls

M:\Mproj\Lenzie\203027\100%\summaries\pta-phase2.xls

PTA MISCELLANEOUS SUMMARIES (2 OF 2)

REG	STATE	PROJECT	SHEET NO.	TOTAL SHEETS
9	HI	HI-A-AD-6(2) SADDLE ROAD	C9	C10

REVISED
03/01/2005

SIGN AND BARRICADE SUMMARY			
Item Number	63507	63504B	63504C
Station	Construction Sign (Road Closed Sign on Type 3 Barricade) (square feet)	Barricade, Type 2 (linear foot)	Barricade, Type 3 (linear foot)
West Entrance	20		40
98+00L	10		10
98+00R	10		10
128+00R	10		10
129+50R	10		10
129+50L	10		10
178+00R	10		10
182+50R	10		10
194+00-196+50L	10	100	10
196+00-197+00R	10	80	10
196+00L	10		10
197+00L	10		10
198+00L	10		10
200+00-203+00R	10	30	10
201+00-203+50L	10	100	10
227+00R	10		10
236+50R	10		10
241+00R	10		10
SCHEDULE A TOTAL	170	310	190
SCHEDULE B TOTAL	190	310	210

EARTH BERM TRANSITION PROTECTION SUMMARY		
Item Number	15735	62901C
Station	Sediment Control Log (each)	Erosion Control Mat, Type 3 (square yard)
91+00L	3	44.5
112+00L	3	44.5
125+50L	3	44.5
137+00L	3	44.5
164+50L	3	44.5
174+00L	3	44.5
190+50L	3	44.5
199+50L	3	44.5
205+00L	3	44.5
213+50L	3	44.5
240+00L	3	44.5
SCHEDULE A TOTAL	27	401
SCHEDULE B TOTAL	33	490

APPROACH ROAD SUMMARY								
Item Number					15212A	20438	30811	61902BH
Station	Access Type	Class	Type	Length (linear foot)	Minor Approach Road Survey and Staking (each)	Grade Access Road (linear foot)	Aggregate Surface Course (ton)	Gate, Metal Type, 16-foot Width (each)
97+00	Fire Access 3	1	A	145	1			1
130+10	Fire Access 4	1	A	180	1			0
182+40	Fire Access 5	1	A	65	1			0
200+00	Makai Road*	2	C	2010	0	2010	559	0
227+35	Fire Access 6	1	A	65	1			0
SCHEDULE A TOTAL					3	2010	559	1
SCHEDULE B TOTAL					4	2010	559	1

*Road for project access

PTA FENCING SUMMARY			
Item Number	20302VA	61901AC	61901FA
Station	Removal of Woven Wire Fence (linear foot)	Fence, Woven Wire Type, 48-inch Height (linear foot)	Fence Temporary Construction (linear foot)
88+00 to 92+00	0	400	785
92+00 to 98+00	550	600	0
98+00 to 111+00	1300	1380	0
111+00 to 126+00	1500	1500	0
126+00 to 127+70	370	170	0
204+00 to 209+00	0	0	550
SCHEDULE A TOTAL	3170	3050	550
SCHEDULE B TOTAL	3720	4050	1335

M:\Mproj\Lenzie\2030271\100%summaries\pta-phase2.xls