

STATE	PROJECT	SHEET NO.	TOTAL SHEETS
HI	HI A-AD 6(7)	B12	B29

AS-BUILT DRAWINGS/SPECIFICATIONS

This certifies that the dimensions and details shown on this sheet reflect the dimensions and details and specifications as constructed in the field.

GOODFELLOW BROS., INC.

Contractor's Name:

Yaim Kew 1/2/14
Signature Date

EROSION CONTROL SUMMARY

Station	to	Station	SOIL EROSION CONTROL, SILT FENCE LNFT 15705-0100	SOIL EROSION CONTROL, CHECK DAM EACH 15706-0200	SOIL EROSION CONTROL, SEDIMENT LOG LNFT 15705-1400	SOIL EROSION CONTROL, MULCHING, HYDRAULIC METHOD ACRE 15703-2500	ROLLED EROSION CONTROL PRODUCT, TYPE 3.B SQYD 62901-1000	REMARKS
Saddle Road								
200+00	to	208+00	0	0	0.171	0.0	0	
208+00	to	222+00	0	0	0.341	0.0	0	
222+00	to	236+00	0	0	0.57	0.0	0	
698+00	to	712+00	579	8	0	0.4	681	
712+00	to	726+00	1,104	4	160	0.6	3,100	
726+00	to	740+00	1,185	0	80.160	0.9	2,773	
740+00	to	754+00	1,186	0	0.48	0.4	584	
Mamalahoa Hwy								
764+00	to	773+00	34	0	160.479	0.0	1,598	
773+00	to	787+00	247	0	180.167	0.0	48	
787+00	to	798+22	100	0	220.352	0.0	1,308	
Old Saddle Road			364	4	0	0.3	100	
Lightning Trail								
1000+00	to	1014+00	1,820	37	10.9	0.7	1,053	
1014+00	to	1028+00	2,317	10	80.93	0.5	796	
1028+00	to	1042+00	349	27	0.32	0.7	701	
1042+00	to	1056+00	2,848	0	0	0.6	0	
1056+00	to	1070+00	2,805	0	0	0.5	0	
1070+00	to	1081+56.99	2,005	0	0	0.4	0	
MSR Road			929	0	0	1	1141	
PROJECT TOTAL			17,872	90	2,069	6.9	13,883	



THIS WORK WAS PREPARED BY ME OR UNDER MY SUPERVISION.
Wendy G. McLain 4/30/2012
 SIGNATURE EXPIRATION DATE OF THE LICENSE

U.S. DEPARTMENT OF TRANSPORTATION
FEDERAL HIGHWAY ADMINISTRATION
CENTRAL FEDERAL LANDS HIGHWAY DIVISION

EROSION CONTROL SUMMARY