

N:\H\h6(5)\Roadway\Sheets\B-Summ\B96-sheets.xls\SumEnglish-Sched A

8/5/08 8:35 AM

ITEM NO.	ITEM DESCRIPTION	Sheet Number-->		B5	B6-B8	B9-B11	B12-B13	B14-B16					ESTIMATED QUANTITIES		STATE	PROJECT	SHEET NO.	TOTAL SHEETS					
		Sheet Description-->											Grading Summaries	Surfacing Summaries	Permanent Sign Summary	Pavement Markers & Striping Summary	Misc. Summaries	PLAN	BID	HI	HI A-AD 6(5) SADDLE ROAD	B1	B16
		UNIT																		REMARKS AND/OR DETERMINATION OF ESTIMATED QUANTITY			
15101	MOBILIZATION	LPSM											ALL	ALL									
15202	SLOPE, REFERENCE, AND CLEARING AND GRUBBING STAKES	MILE						0.85					0.85	0.9									
15203	CENTERLINE RE-ESTABLISHMENT	MILE						7.21					7.21	7.3									
15204	DRAINAGE STRUCTURE SURVEY AND STAKING	EACH						2					2	2									
15207	GRADE FINISHING STAKES	MILE						7.21					7.21	7.3									
15212A	MINOR APPROACH ROAD SURVEY AND STAKING	EACH						3					3	3									
15301	CONTRACTOR QUALITY CONTROL	LPSM											ALL	ALL									
15501	CONSTRUCTION SCHEDULE	LPSM											ALL	ALL									
15703	SILT FENCE	LNFT						13793					13793	14350									
15709	CHECK DAMS	EACH						150					150	155									
15735	SEDIMENT CONTROL LOG	EACH						276					276	290									
15805	WATERING	MGAL												10000									
20101	CLEARING AND GRUBBING	ACRE						10.69					10.69	11.2									
20302RA	REMOVAL OF ASPHALT CURB	LNFT						500					500	520									
20402	SUBEXCAVATION	CUYD												2000									
20403	UNCLASSIFIED BORROW	CUYD		23648									23648	24700									
20409	EMBANKMENT CONSTRUCTION	CUYD		28094									28094	29300									
21101	ROADWAY OBLITERATION	SQYD						618					618	650									
25101C	PLACED RIPRAP, CLASS 3	CUYD						22					22	23									
25111	PLACED INDIVIDUAL BOULDERS	EACH						41					41	45									
25206	ROCKERY WALL	SQFT						1241					1241	1300									
30104E	SUBBASE, GRADING E	TON			6455			25226					31681	33000									
30302	ROAD RECONDITIONING	SQYD						156860					156860	164000									
30612	DUST PALLIATIVE	GAL												25000									
30701LA	STOCKPILED AGGREGATE, 3" GRADING	TON												10200	<i>> Deleted by cm 002</i>								
30701LB	STOCKPILED AGGREGATE, 6" GRADING	TON												8400									
40501E	HOT ASPHALT TREATED BASE COURSE, GRADING E	TON			74693								74693	77700									
40504C	ANTISTRIP ADDITIVE, TYPE 3	TON			746.9								746.9	780									
40505PGDB	ASPHALT BINDER, GRADE 64-16	TON			4706								4706	5000									
40507	MATERIALS TRANSFER VEHICLE	LPSM											ALL	ALL									
40908BA	FOG SEAL GRADE CSS-1 OR CSS-1H, SS-1 OR SS-1H	TON			37.85								37.9	40									
41101CM	PRIME COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON			113.55								113.55	119									
41201CM	TACK COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON			37.85			0.48					38.3	40									
41301F	ASPHALT PAVEMENT MILLING, 2-INCH DEPTH	SQYD						1955					1955	2040									
60104	CONCRETE (PEDESTRIAN PAD)	EACH						8					8	8									
60104	CONCRETE (HOLE FOUNDATION)	EACH						8					8	8									
60201M	24-INCH PIPE CULVERT	LNFT						14					14	15									
60201N	30-INCH PIPE CULVERT	LNFT						176					176	184									
60206N	END SECTION FOR 30-INCH PIPE CULVERT	EACH						2					2	2									
60223	REMOVE AND RESET END SECTION	EACH						1					1	1									
61701BBAA	GUARDRAIL SYSTEM G2, TYPE 2, CLASS A (STEEL POSTS)	LNFT											350	375									
61702EA	TERMINAL SECTION TYPE EXTRUDER (ET 2000 PLUS)	EACH											1 2	1 2	<i>2 Item not used</i>								
61702FL	TERMINAL SECTION TYPE FLARED (TYPE A)	EACH											1	1									
61901AC	FENCE, WOVEN WIRE TYPE, 48-INCH HEIGHT	LNFT						35804					35804	37300									
61901FA	FENCE TEMPORARY CONSTRUCTION	LNFT												2000									
61902BG	GATE, METAL TYPE, 14-FOOT WIDTH	EACH						7					7	7									
61902BK	GATE, METAL TYPE, 20-FOOT WIDTH	EACH						3					3	3									
61906	REMOVE AND RESET FENCE	LNFT						500					500	520									
62201AE	DUMP TRUCK, 10-12 CUBIC YARD CAPACITY	HOUR												20	<i>Item Not Used</i>								
62201BC	BACKHOE LOADER, 48 GAL MINIMUM RATED CAPACITY BUCKET (24-INCH WIDTH)	HOUR												20									
62201CE	LOADER, WHEEL TYPE, 4 CUBIC YARD MINIMUM CAPACITY	HOUR												20									
62201DG	BULLDOZER, D-9	HOUR												60									

The following quantities are approximate unless noted as a contract quantity. Payment will be made for the actual quantities of work performed and accepted or for materials furnished according to the contract.

SUMMARY OF QUANTITIES
SCHEDULE A

[illegible]

ITEM NO.	ITEM DESCRIPTION	Sheet Number-->		B5	B6-B8	B9-B11	B12-B13	B14-B16					ESTIMATED QUANTITIES	STATE	PROJECT	SHEET NO.	TOTAL SHEETS
		Sheet Description-->												HI	HI A-AD 6(5) SADDLE ROAD	B4	B16
		UNIT												REMARKS AND/OR DETERMINATION OF ESTIMATED QUANTITY			
														PLAN	BID		
15101	MOBILIZATION	LPSM											ALL	ALL			
15301	CONTRACTOR QUALITY CONTROL	LPSM											ALL	ALL			
30104E	SUBBASE, GRADING E	TON			12835			1964					14799	15400			
40103PGDB	ASPHALT CEMENT GRADE PG 64-16	TON			1735.9								1735.9	1810			
40105C	ANTISTRIP ADDITIVE, TYPE 3	TON			255.3								255.3	270			
40106ABBL	SUPERPAVE ASPHALT CONCRETE PAVEMENT, 1/2-INCH NOMINAL MAXIMUM SIZE AGGREGATE	TON			25528								25528	26600			
40107	MATERIALS TRANSFER VEHICLE	LPSM											ALL	ALL			
40908BA	FOG SEAL GRADE CSS-1 OR CSS-1H, SS-1 OR SS-1H	TON			6.83								6.83	8			
41101CM	PRIME COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON			20.75								20.75	22			
41201CM	TACK COAT GRADE CSS-1, CSS-1H, SS-1, OR SS-1H	TON			6.74								6.74	7			
60905K	ASPHALT CONCRETE CURB, 4-INCH DEPTH	LNFT						36304					36304	37800			
62101	MONUMENT	EACH											31	33			
62201AE	DUMP TRUCK, 10-12 CUBIC YARD CAPACITY	HOUR												5		<i>Item Not Used</i>	
62201BC	BACKHOE LOADER, 48 GAL MINIMUM RATED CAPACITY BUCKET (24-INCH WIDTH)	HOUR												5		<i>Item Not Used</i>	
62201CE	LOADER, WHEEL TYPE, 4 CUBIC YARD MINIMUM CAPACITY	HOUR												5			
62201DG	BULLDOZER, D-9	HOUR												5		<i>Item Not Used</i>	
62201LB	MOTOR GRADER, 12 FOOT MINIMUM BLADE	HOUR												5		<i>Item Not Used</i>	
62201MT	HYDRAULIC EXCAVATOR, TRACK TYPE, 165 HP FLYWHEEL POWER, 1.3 CUBIC YARD BUCKET, EQUIVALENT TO A CATERPILLAR 225B, WITH A RAM HOE	HOUR												5		<i>" " "</i>	
62301	GENERAL LABOR	HOUR												20		<i>" " "</i>	
63401IA	PAVEMENT MARKINGS TYPE I, SOLID (4-INCH)	LNFT					88879						88,879	93,300			
63401IA	PAVEMENT MARKINGS TYPE I, SOLID (8-INCH)	LNFT					76102						76,102	79,600			
63401IA	PAVEMENT MARKINGS TYPE I, SOLID (12-INCH)	LNFT					5319						5,319	5,550			
63401IB	PAVEMENT MARKINGS TYPE I, BROKEN	LNFT					1233						1,233	1,290			
63405	RAISED PAVEMENT MARKERS	EACH					6950						6,950	7,250			
63406	PAVEMENT MARKINGS, SYMBOLS	EACH					52						52	52			
63408	RUMBLE STRIP	MILE											21	22			
63509	FLAGGER	HOUR						300					300	300		<i>Item Not Used</i>	