

DATE _____
SURVEY PLOTTED BY _____
DESIGNED BY _____
NOTED BY _____
QUANTITIES BY _____
CHECKED BY _____
No. _____

STATION	LEFT	RIGHT	TYPE	REMOVE	INSTALL			
					10 Sq. FT. or Less		GREATER THAN 10 Sq. FT.	
					W/POST	%POST	W/POST	%POST
109+80		•	W1-G(R) *		1			
110+15		•	W1-G(L) *		1			
115+50	•		W1-1(R) w/ Supplemental W13-1(15)		1	1		
120+05	✕		ROAD ENDS AHEAD (15" x 48")	2			≠	
123+18	•		R2-1(35) a (36" x 48")	1			1	
123+18	•		R2-1(45) a (36" x 48")	1			1	
129+12	•		R2-5b(35) a (36" x 48")	1			1	
135+11	•		R1-1	1	1			
168+97	•		R2-5b(35) a (36" x 48")	1			1	
170+96	•		W2-1	1				
174+00	•		W2-#2(L)		1			
176+00	•		R2-1(45) a (36" x 48")	1			1	
176+00	•		R2-1(35) a (36" x 48")	1			1	
178+37	•		R1-1	1	1			
178+79	✕		R1-1	≠	≠			
180+60	•		W2-#2(L)	1	≠			
182+80	•		R1-1	1	1			
184+80	•		R1-1	1	1			
199+21	•		R2-1(35) a (36" x 48")	1			1	
199+21	•		R2-1(45) a (36" x 48")	1			1	
205+08	•		R2-5b(35) a (36" x 48")	1			1	
244+20	•		R2-1(45) a (36" x 48")	2			2	
253+02	•		R1-1	1	1			
253+25	•		R1-1	1	1			
283+17	•		R2-5b(35) a (36" x 48")	1			1	
287+43	•		R2-1(45) a (36" x 48")	1			1	
287+43	•		R2-1(35) a (36" x 48")	1			1	
294+40	•		R1-1	1	1			
297+58	•		R1-1	1	1			
326+78	•		R1-1	1	1			
329+25-65	•		R4-1		1			
332+81	•		R2-1(35) a (36" x 48")	1			1	
333+81	•		R2-1(45) a (36" x 48")	1			1	
338+25	•		R4-2		1			
340+35	•		R2-5b(35) a (36" x 48")				1	
354+10	•		R4-1	1				
361+30	•		R4-2	2				
361+75	•		R4-2		1			
367+88	•		R4-1	1				
370+10	•		R4-1		2			
372+43	•		R4-1	1				
373+00	•		W1-4(L)	1	1			
378+50	•		R4-2		1			
379+53	•		R4-2	1				
386+61	•		R4-2	1				
387+50	•		R4-2		1			
393+73	•		R4-1	1				
395+12	•		W1-4(L)	1	1			
396+00	•		R4-1		2			
403+94	•		W2-1	1	1			
409+12	•		R1-1	1	1			
409+93	•		R1-1	1	1			
414+53	•		W2-1	1	1			
426+00	•		R2-5b(35) a (36" x 48")	1			1	
427+48	•		W11A-2=2	1	1			
429+85	•		R2-1(45) (36" x 48")	1			1	
CONTINUED				47	10		20	
433+30	•		W11A, W11-2P		1			
434+00	•		W11A, W11-2P		1			

STATION	LEFT	RIGHT	TYPE	REMOVE	INSTALL			
					10 Sq. FT. or Less		GREATER THAN 10 Sq. FT.	
					W/POST	%POST	W/POST	%POST
429+85		•	R2-1(35) (36" x 48")	1			1	
432+00		•	W1-4(R)		1			
435+40		•	R1-1	1	1			
437+71	•		R2-1(35) a (36" x 48")	1			1	
437+71	•		R2-1(45) a (36" x 48")	1			1	
439+00	•		W11A-2=2 W11-2	1	1			
441+72	•		R2-5b(35) a (36" x 48")	1			1	
441+72	•		R2-4(30)	1				
456+48	•		W1-2(R)	1	1			
460+00	•		W1-4(R)	1	1			
472+98	•		W1-2(L)	1	1			
485+00	•		W2-1	1				
487+00	•		W2-#2(L)		1			
489+60	•		R7-1	1	1			
490+61	•		R7-1	1	1			
491+35	•		R7-1	1	1			
491+55	•		R1-1	1	1			
492+23	✕		R1-1	1	≠			
493+28	•		R4-1	1				
494+10	•		R2-4	1				
497+67	•		W2-#2(R)	1	1			
498+25	•		R2-5b(25) a (36" x 48")				1	
499+48	✕		R1-1	1	≠			
500+34	•		R4-2	1				
501+42	•		W1-4	1				
502+25	•		R2-1(45) (36" x 48")	1			1	
502+25	•		R2-1(25) (36" x 48")	1			1	
512+43	•		R1-1	1	1			
520+15	•		R1G-7	1	1			
520+26	•		R1-1	1	1			
520+33	•		R1-1	1	1			
523+13	•		R3-8a (36" x 36")	1	1			
525+17	•		R7-1	2	2			
527+08	•		R3-4	1	1			
527+14	•		R7-1	1	1			
527+23	•		R7-1	1	1			
527+30	•		D9-2 (36" x 36") w/ SUPPLEMENTAL "HOSPITAL" & ARROW	1	1	2		
527+82	•		R1-1	1	1			
529+43	•		R2-1(25)	1		1		
536+91	•		R1-1	1	1			
537+26	•		R1-1	1	1			
541+95	•		R1-1	1	1			
544+51	•		R1-1	1	1			
545+97	•		R1-1	1	1			
547+46	•		R2-1(25)	1	1			
548+51	•		R1-1	1	1			
548+51	•		S1-1	1		1		
549+37	•		R1-1	1	1			
550+03	•		R8-3	1	1			
550+95	•		R2-1(25)	1	1			
551+65	•		R1-1	1	1			
552+00	•		R7-1	1	1			
553+47	•		S1-1	1	1			
554+53	•		R1-1	1	1			
555+28	•		W1-2(L)	1	1			
CONTINUED				41	41	5	7	
495+90	•		W1-4(R)		1			
508+25	•		W1-4(R)		1			

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	240A-01-92M	1992	30	31

STATION	LEFT	RIGHT	TYPE	REMOVE	INSTALL			
					10 Sq. FT. or Less		GREATER THAN 10 Sq. FT.	
					W/POST	%POST	W/POST	%POST
555+90		•	S2-1		1			
556+34		•	R7-1	1				
0+19	•		R1-1	1	1			
1+35	•		S2-1		1			
2+26	•		S2-1	1				
2+540	•		W2-2	1	1			
3+60	•		S1-1	1	1			
3+92	•		R1-1	1	1			
4+99	•		R1-1	1	1			
5+45	•		R2-1(25) a (36" x 48")	1			1	
5+45	•		W1-2(R)	1	1			
5+95	•		R2-1(40) a (36" x 48")	1			1	
8+00	•		W2-2	1	1			
11+17	•		R2-5b(25) a (36" x 48")	1			1	
13+54	•		W1-2(L)	1	1			
26+00	•		R2-1(40) a (36" x 48")	2			2	
27+20	•		W1-4(R)	1	1			
32+00	•		R1-1	1	1			
35+450	•		W2-2(R)	1	1			
37+50	•		W1-2(L)	1				
38+43	•		R1-1	1	1			
41+587	•		W2-2(L)		1			
42+84	•		R1-1	1	1			
44+05	•		W1-4(R)	1	1			
47+90	✕		R2-1(40) a (36" x 48")	≠			≠	
45+2815	•		W2-4	1	1			
SIDEROADS:								
178+68	•		W1-1(R), W13-1(25)	1	1	1		
	•		W3-1	1	1			
	•		W1-8	1				
	•		R2-1(25)	1	1			
	•		R5-1a (WRONG WAY)	1	1			
	•		R5-1	1	1			
	•		R1-1	1	1			
	•		W5-1	1	1			
4+71	•		R5-1	1	1			
	•		R6-1(L)	1	1			
4+15	•		R7-1	1	1			
3+15	•		R7-1	1	1			
TOTALS				136	102	6	33	
				135	103		31	

NOTE:
* W1-G Large arrow sign shall be installed with two (2) posts.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION
SIGN SCHEDULE

HONOKAA-WAIPIO ROAD RESURFACING
PROJ. No. 240A-01-92M
HAMAKUA, HAWAII
Date: April, 1992
SHEET No. 1 OF 1 SHEETS