

SIGN REPLACEMENT, REMOVAL, AND INSTALLATION SCHEDULE

STATION	MAUKA	MAKAI	TYPE	SIGN TO REMAIN	REMOVE	INSTALL (10 SQ. FT. OR LESS)		DESTINATION SIGN PANEL (S.F.)
						W/POST	WO/POST	
Segment A	Right	Left						
119+90		●	W (Caution: Windy Road...)	1				
119+85		●	W1-8 (Bi-Directional)		1			
119+50		●	W1-8 (Bi-Directional)		1	1	1	
119+15		●	W1-8 (Bi-Directional)		1			
118+80 to 117+40		●	W1-8 (Bi-Directional)		1	3	3	
118+35		●	RI-1		1	1		
118+25	●		RI-1/D3-1 (IKI RD.)		2	1	1	
117+00		●	W1-5 (R)/W13-1 (25)			1	1	
115+70	●		W2-2h(R)/W (Hidden Driveway) (24"x18")/D3-2 (IKI RD.)		2	1	1	
115+30		●	W1-5 (R)/W13-1 (25)		2			
114+80	●		W1-1 (R)/W13-1 (25)		2	1	1	
113+85	●		D-1 (Elevation/1500 ft/457 m) (30"x18")		1			3.75
113+75		●	D-1 (Elevation/1500 ft/457 m) (30"x18")		1			3.75
110+60 to 108+10	●		W1-8 (Bi-Directional)			6	6	
104+50		●	W2-2 (L)/W13-1 (25)		2	1	1	
101+70	●		RI-1		1	1		
100+20 to 98+20		●	W1-8 (Bi-Directional)			5	5	
98+75	●		W2-2 (R)/W13-1 (25)		2	1	1	
95+55 to 93+55		●	W1-8 (Bi-Directional)			5	5	
90+00	●		W1-5 (R)/W13-1 (25)		2	1	1	
84+50		●	W1-1 (R)/W13-1 (25)		2	1	1	
80+20 to 78+80		●	W1-8 (Bi-Directional)			3	3	
73+95	●		W1-1 (R)/W13-1 (25)		2	1	1	
7+30		●	W1-2 (R)		2	1		
4+95		●	W2-2 (R)		1	1		
Segment B	Left	Right						
0+75		●	RI-1		1	1		
2+20		●	W1-4 (R)		2	1		
2+50	●		W1-2 (L)		2	1		
2+70		●	"Adopt-A-Highway"	1				
5+50	●		W2-2		1	1		
5+60	●		"Adopt-A-Highway"	1				

STATION	MAUKA	MAKAI	TYPE	SIGN TO REMAIN	REMOVE	INSTALL (10 SQ. FT. OR LESS)		DESTINATION SIGN PANEL (S.F.)
						W/POST	WO/POST	
Segment B	Left	Right						
5+95	●	●	D-2 (Elevation/2000 ft/610 m) (30"x18")		2			7.50
14+15	●		W1-4 (R)		2	1		
23+50		●	W1-4 (L)		2	1		
43+00	●		W1-4 (L)		2	1		
59+55		●	R2-1 (35) -A	1				
111+45	●	●	D-3 (Elevation/2500 ft/762 m) (30"x18")		2			7.50
115+85		●	"Adopt-A-Highway"	1				
116+05	●		"Adopt-A-Highway"	1				
121+35		●	W1-4 (L)		2	1		
128+35		●	W1-8 (Bi-Directional)			1	1	
128+80		●	W1-8 (Bi-Directional)		1			
129+15		●	W1-8 (Bi-Directional)			1	1	
129+25		●	W1-8 (Bi-Directional)		1			
129+95 to 130+75		●	W1-8 (Bi-Directional)			2	2	
135+85	●		W1-8 (Bi-Directional)		1			
135+05 to 136+85	●		W1-8 (Bi-Directional)		1	3	3	
142+05	●		W1-4 (L)		2	1		
165+30	●	●	R2-1 (35) -A	2				
166+10		●	W (Horse and Ranch Xing...)	1				
204+00 to 206+10	●		W1-8 (Bi-Directional)			4	4	
218+70	●		"Adopt-A-Highway"	1				
219+65		●	"Adopt-A-Highway"	1				
TOTALS				11	53	56	43	22.50

NOTE :

- Street Name sign D3-1 shall be paid for under item 621.500 - Regulatory and Warning Sign (10 square feet or less) w/out Posts.
- Fabrication and installation of Supplemental Street Name sign D3-2 shall be considered incidental to installation of W2-1 and W2-2 signs, as applicable.
- Destination signs shall be installed with a single 2" square tube post.
- Square tube sign posts required for the installation of destination signs shall be considered incidental to Item No. 621.0200 - Panel for Destination Sign.
- W1-8 signs shall be installed with its face perpendicular to the roadway centerline.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SIGN SCHEDULE

KOHALA MOUNTAIN ROAD RESURFACING
IKI ROAD TO KAHUA
PROJECT NO. 250A-01-96M

Date: March, 1996

SHEET No. 1 OF 1 SHEETS

SURVEY PLOTTED BY	DATE
PLAN	
NOTE BOOK	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	