

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	STP-250(006)	2011	18	20

STRIPING AND PAVEMENT MARKING SCHEDULE

STATION		TRAFFIC REGIME		THERMOPLASTIC EXTRUSION (lin. ft.)					PAVEMENT MARKERS (EACH)			
FROM	TO	LEFT	RIGHT	4" Double Yellow	4" Single Yellow	4" White E.P. Stripe	8" White E.P. Stripe	12" Stop Bar	C	D	H	J
569+50	602+50	N	N	3,300 3,244		6,600 6,488			165 163	165 163		
602+44	608+27	N	P		577 563	1,154 1,166			29 28	14	14	56
608+27	609+44	N	N	128 117		256 234			6	6		
609+44	611+45	P	N		190 207	380 402			10 13	5 6	5	20
611+45	613+98.40	P	P			507 550			14 14	7		28
	614+19.30	P	P									
614+19.30	614+20	P	P			1			0	0		
614+20	618+44	N	P		424	848			0 22	11	11 12	44 48
618+44	621+21	P	P			554			14	7		28
621+21	628+18	P	N		697	1,394			35 36	17 18	17 18	68 72
628+18	646+88	N	N	1,870		3,740			94	94		
646+88	651+98	N	P		510	1,020			26 15	13 15	13 12	52 48
651+98	653+88	N	N	290 190		580 380			10 10	10 10		
653+88	658+98	P	N		410 510	820 1,020			21 26	10 13	10 12	40 48
658+98	666+69	N	N	771		1,542			39 40	39		
666+69	670+99	N	P		430	860			22	11	10 10	44 40
670+99	673+69	N	N	270		540			14	14		
673+69	678+00	P	N		431	862			22	11 12	11	44
678+00	683+42.68	N	N	543		1,085			27	27		
	683+61.50	N	N	7,941		15,882			398	398		
683+61.50	755+20.07	N	N	7,159		14,317			358	358		
	757+81.20	N	N	7,941		15,882			398	398		
757+81.20	760+42	N	N	261		522			13	13		
760+42	760+82	Sideroad		15 20		100 84		22 25	2	3		
760+82	764+79	N	N	397 395		794 790			20	20		
764+79	765+29	N	P	60	50 100	120 100			3 4	3 2	2 2	8 8
765+29	765+69	Driveway		40 20	40 80	150 80		15 25	4 2	5 3		
765+69	766+54	N	P	85	85 170	170			4 6	4 3	3 3	12 12
766+54	766+94	Driveway		20	40 80	110 80		14 25	2	3		
766+94	769+30	N	P	236	235 470	472 470			12	12 6	6 6	24 24
769+30	770+40	N	P	110		220 110			6	3 3		12 12
770+40	772+49	P	N	209	209 418	418			10 12	10 6	6 6	24 24
772+49	772+85	Driveway		15 20	36 72	82 164		15 25	2	3		
772+85	773+34	N	N	49	220 440	440			12 12	6 6	6 6	24 24
773+34	775+47	N	N	213		426			11	11		
ESTIMATED TOTALS				16,040 14,907	3,669 4,701	39,580 39,366	1,214 1,102	66 100	996 1,026	917 894	92 117	368 536
CONTRACT ITEM NUMBER				629.1013 629.1010	629.1011 629.1010	629.1012 629.1010	629.1015 629.1010	629.1018 629.1010	629.2030	629.2040	629.2070	629.2080

CENTERLINE MONUMENT SCHEDULE

EXISTING PROJECT	STATION	RECONSTRUCT (Item No. 613.0300)	ADJUST EXISTING (Item No. 613.0300)	CENTERLINE OFFSET (FT.)	REMARKS
S-239 (H)	(R/W) P.T. 569+87.36	±		0.00	ADD. No. 1
FAP E-11-A	P.O.C. 570+00	±	1	0.00	
	P.T. 650+18.88		1		
	P.T. 659+93.47	±	1	1.20 R.T.	
	P.C. 660+90.91	±	1	0.70 R.T.	
	P.T. 668+32.58	±	1	1.20 L.T.	
	P.T. 683+42.68 BK P.T. 683+61.50 AH	±	1	1.00 L.T.	
	P.C. 685+77.90	±	1	0.00	
	P.T. 688+97.87	±	1	1.20 R.T.	
	P.C. 694+93.63	±	1	0.20 L.T.	
	P.T. 700+69.59	±	1	0.40 L.T.	
	P.C. 704+54.46		1		
	P.T. 709+34.31	±	1	1.50 L.T.	
	P.T. 712+52.02	±	1	1.90 L.T.	
	P.C. 717+78.77	±	1	1.80 L.T.	
	P.T. 721+88.48	±	1	1.20 R.T.	
	P.C. 722+12.04	±	1	0.00	
	P.T. 746+49.28	±	1	1.00 L.T.	
	P.C. 746+50.87	±	1	1.00 R.T.	
	P.T. 750+37.88	±	1	0.90 L.T.	
TOTAL		18 0	18 19		

SURVEY PLOTTED BY	DATE
DRAWN BY	
NOTE BOOK	
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	

LEGEND FOR AS-BUILT POSTINGS	
	Squiggly line for as-built deletion
	Double line for as-built deletion
Roadway	Text for as-built posting

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

**PAVEMENT MARKING AND
MONUMENT SCHEDULE**
KOHALA MOUNTAIN ROAD
PAVEMENT PREVENTIVE MAINTENANCE
WAIAKA JUNCTION TOWARD HAWAII
Federal Aid Project No. STP-250(006)
Date: April, 2011

SHEET No. 1 OF 1 SHEETS

"AS-BUILT"