

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	270B-01-93M	1993	3	27

GENERAL NOTES:

1. The scope of work for this project consists of cold planing; reconstructing weakened pavement areas; leveling and resurfacing the existing pavement; replacing and installing pavement markings.

2. The Contractor's attention is directed to Subsection 107.13 - Public Convenience and Safety; Section 645 - Traffic Control and Subsection 107.21 - Contractor's Responsibility for Utility Property and Service of the Special Provisions.

3. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.

4. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.

5. The exact locations and limits or areas to be filled with leveling course, reconstructed and cold planed shall be determined in the field by the Engineer.

6. The Contractor shall notify the State in writing, two (2) weeks prior to starting paving operations.

7. The Contractor shall remove and dispose of all existing pavement markings prior to the overlaying of Asphalt Concrete. This work shall be considered incidental to Asphalt Concrete Pavement, Mix No. IV and will not be paid for separately.

8. Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.

9. Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to accomplish maintenance of flow, the cost of which shall be considered incidental to the various contract items.

10. Contractor shall provide for access to and from all existing driveways and streets at all times.

11. All saw cutting work shall be considered incidental to Roadway Excavation.

12. Existing pavement surface variable, surface indicated here is not intended to represent any specific location.

13. Whenever a definite widening of the existing pavement is evident on curved sections of the highway, resurfacing shall be carried to the limits of the pavement utilizing either full depth pavement or tapers as necessary.

14. Asphalt Concrete for leveling shall be paid for under Item No. 401.0400 - Asphalt Concrete Pavement, Mix No. IV.
15. Prime coat/ Tack coat shall be incidental to Item No. 401.0400 - Asphalt Concrete Pavement, Mix No. IV.

16. Contractor's attention is directed to Section 401.03 of the Special Provisions. All longitudinal and transverse tapers within the traveled way shall be removed prior to commencing and continuing of paving operations.

LEGEND

- Reconstruction Areas
- Resurfacing Limits
- Existing Guy Pole
- Existing Power Pole
- Existing Service Pole
- Existing Valve Box
- Existing Water Valve Box
- Existing Fire Hydrant
- Existing Water Meter
- Existing Boundry Pipe

SURVEY PLOTTED BY	DATE
DRAWN BY	10-15-92
DESIGNED BY	
QUANTITIES BY	
CHECKED BY	

ORIGINAL PLAN
NOTE BOOK
logIn Jason
N. Jorjoo

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

POLOLU VALLEY ROAD RESURFACING

Project No. 270B-01-93M

Date: Oct., 1992