

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	270A-01-96M	1996	3	28

GENERAL NOTES

- SURVEY PLOTTED BY
DATE
DESIGNED BY
DESIGNED BY
NOTE BOOK
QUANTITIES BY
CHECKED BY
No.

ORIGINAL
PLAN
No.

1. This project consists of leveling and resurfacing the existing pavement; installing paving fabric; reconstructing and adjusting reference survey monuments; replacing and installing signs and installing pavement striping, marking and markers; and adjusting water valves.

2. The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 – Public Convenience and Safety, and Section 645 – Traffic Control.

3. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.

4. The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operation.

5. All holes, depressions and wheel ruts shall be filled and compacted with Asphalt Concrete Pavement, Mix No. V prior to resurfacing. This work will be paid for under Item 401.0500, Asphalt Concrete Pavement, Mix No. V.

6. The exact locations and limits of areas to be filled with leveling course, reconstructed and cold planed shall be determined in the field by the Engineer.

7. The Contractor shall notify the Engineer in writing, two (2) weeks prior to starting paving operations.

8. The Contractor shall remove and dispose of all existing raised pavement markers prior to the overlaying of Asphalt Concrete Pavement, Mix No. IV.

9. Existing Thermoplastic Extrusion Pavement Markings and Preformed Pavement Marking Tape shall be removed prior to resurfacing. Removal shall be by scraping, grinding or other method approved by the Engineer. This work shall be considered incidental to Item No. 401.0400, Asphalt Concrete Pavement, Mix No. IV.

10. Smooth riding connections shall be constructed at all limits of resurfacing including the beginning and end of project, connecting approaches, side streets, and driveways and at the ends of the daily work areas as shown on the plans and/or as directed by the Engineer. This work shall be considered incidental to the various contract items and will not be paid for separately.

11. Contractor shall be responsible for initial preparation, finish rolling, and maintaining the shoulders. This work shall be considered incidental to Item No. 401.0400, Asphalt Concrete Pavement, Mix No. IV.

12. Existing drainage system will be functional at all items during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.

13. Contractor shall provide safe access to and from all existing side streets at all times.

14. The Contractor is reminded of the requirements of Subsection 108.01– Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.

15. During non-working hours, the Contractor shall provide a 2' wide longitudinal feathered taper for all pavement drop offs greater than 2". Feathered taper shall not exceed 0.75 miles in length at non-intersection areas. Feathered tapers shall be removed prior to the placing of the final overlay. Payment of feathered tapers shall not be measured and will be considered incidental to Item 401.0400, Asphalt Concrete Pavement, Mix No. IV.

16. Cold-planing transitions at begin and end of project shall be incidental to Item No. 401.0400, Asphalt Concrete Pavement, Mix No. IV.

17. Contractor shall maintain at least one pave shoulder free and clear of debris for pedestrian and bicycle traffic at all times.

18. Contractor shall schedule his work around the annual Ironman Triathlon Race activities. All pavement and shoulder areas shall be restored to smooth riding condition, completely cleaned, and pavement striping installed prior to October 9, 1996. No construction work shall be permitted between October 9, 1996 and October 28, 1996.

19. Removal of existing reflector and object markers and posts is required and this work is considered incidental to the applicable contract items.
- LEGEND
- R/W

E.P.

E.S.

A.C.

RIGHT OF WAY

EDGE OF PAVEMENT

EDGE OF SHOULDER

ASPHALTIC CONCRETE
-
- STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES

& LEGEND

AKONI PULE HIGHWAY RESURFACING

Mile Post 6.90 to 3.43

Project No. 270A-01-96M

Scale: None

Date: May 1996

SHEET No. 1

OF 1

SHEETS
- 3