

FED. ROAD DIST.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	2000E-02-00M	2000	3	6

GENERAL NOTES

- The project includes cold planing the existing pavement, installing white-topping, and replacing pavement markings and traffic signal loops.
- The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
- The Contractor's attention is directed to the following sections of the Special Provisions: Subsection 107.13 - "Public Convenience and Safety", Subsection 107.21 - Contractor's Responsibility for Utility Property and Services, and Section 645 - Traffic Control.
- The Contractor shall notify the State in writing two (2) weeks prior to starting white-topping operations.
- The Contractor shall provide for access to and from all existing side streets and Driveways at all times. This work shall be considered incidental to the various contract items and will not be paid for separately.
- Unprotected pavement dropoffs shall not be allowed during non-working hours, except where approved by the Engineer in writing.
- Smooth riding connections shall be constructed with existing asphalt concrete including the beginning and end of project, connecting approaches, side streets and driveways as shown on the plans and/or as directed by the Engineer.
- The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.
- Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.
- All pavement saw cutting work shall be considered incidental and will not be paid for separately. Saw cutting limits to be determined in the field by the Engineer.
- Public Notice is required for lane closures. Contractor shall submit notice to the Engineer for approval a minimum of six weeks prior to publication. Pre-approval of notice, with dates left blank, is permissible.
- The Contractor shall be solely responsible for the protection of adjacent properties, utilities and existing structures from damages due to construction. Repairing any damage shall be at the Contractor's own expense, to the satisfaction of the Engineer.

CONSTRUCTION NOTES

Site-Specific BMP Submittal Requirements:

- The Contractor shall submit to the Engineer four (4) sets of Site-Specific Best Management Plans (BMP). The Plans shall be submitted no later than thirty calendar days after the award of Contract.
- No construction activities will be authorized until the Contractor's Site-Specific BMP has been approved by the Highways Division.

Grading Notes:

- The Contractor shall remove all silt and debris deposited in drainage facilities, roadways and other areas resulting from his work. The costs incurred for any necessary remedial action by the DPW shall be payable by the Contractor.
- The Contractor, at his own expense, shall keep the project and surrounding areas free from dust nuisances. The work shall be in conformance with the Air Pollution Control rules of the State Department of Health, HAR 11-60J, Fugitive Dust.

LEGEND

- Existing Fire Hydrant
- Existing Monument
- Existing Traffic Sign With 1 Post
- Existing Highway Lighting Standard
- Existing Traffic Signal Pullbox

ORIGINAL PLAN	SURVEY PLATTED BY	DATE
NOTE BOOK	DRAWN BY	5/15/00
QUANTITY BY	DESIGNED BY	
CHECKED BY		

HIGHWAYS DIVISION
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

PUAINAKO STREET WHITE-TOPPING
VICINITY OF IWALANI STREET
PROJ. NO. 2000E-02-00M

Scale: None Date: May, 2000

SHEET No. 1 OF 1 SHEETS