CONSTANT CURRENT REGULATOR (CCR) SCHEDULE						
CCR NO.	CKT ID.	SIZE	OUTPUT CURRENT	NUMBER OF STEPS	LOAD	DESCRIPTION
R-1	R-1	15KW	6.6A	5	9.1KW	RWY 17/35 HIRL EDGE LIGHT & DISTANCE REMAINING SIGNS
T-1	T-1	30KW	6.6A	3	2.1KW	TWY B EDGE LIGHTS AND SIGNS
R-2	R-2	7.5KW	6.6A	3	7.3KW	RWY 3/21 MIRL EDGE LIGHTS & DISTANCE REMAINING SIGNS
T-2	T-2	30KW	6.6A	3	6.4KW	TWY'S A, B AND D EDGE LIGHTS AND SIGNS
T-3	T-3	30KW	6.6A	3	9.5KW	TWY A EDGE LIGHTS AND SIGNS
SP-1	SP-1	30KW	6.6A	5	-	SPARE 5-STEP CCR
SP-2	SP-2	30KW	6.6A	3	-	SPARE 3-STEP CCR

Airports Division
DEPARTMENT OF TRANSPORTATION
STATE OF HAWAII

CHRISTOPHER T. BRISKORN
LICENSED PROFESSIONAL ENGINEER
PE-19550
HAWAII, U.S.A.

4/30/24
Expiration Date

CHRIS BRISKORN, PE
ELECTRICAL ENGINEER

DSGN.	DRWN.	CHKD.	APPD.
HF	HT	JB	DY

KEY PLAN / NOTES:

NO.	DATE	REVISIONS

CONSTRUCTION DOCUMENTS
JULY 2022
DATE

PROJECT TITLE :

RELOCATE RUNWAY 3-21

AT
LIHUE AIRPORT
LIHUE, KAUAI, HAWAII

PROJECT NO.:

AK1031-14

SHEET TITLE:

SIGNS - CCR SCHEDULE

DATE : **07/2022**

SHEET : 375 OF 376 SHEETS

DWG. NO. E5.03

C:\USERS\GALLARDOA\BOX\LIHUE RSA\90-CAD-GIS\90-CAD\20-SHEETS\E5.03.DWG